



Halifax Regional  
School Board

# TENDER #3694

## MOD BIT ROOF REPLACEMENTS PACKAGE #2

Closing Date: **TUESDAY, AUGUST 5, 2014**  
Closing/Opening Time: **2:00:00 P.M.**

**Closing Location:**

Halifax Regional School Board  
33 Spectacle Lake Drive  
Dartmouth, N.S. B3B 1X7

**HRSB Contacts:**

Deborah Beck, Buyer  
Tel: (902) 464-2000 #2011  
Fax: (902) 464-0161

**School Location:**

**Prospect Road**, 2199 Prospect Rd Hatchet Lake NS  
**J L Ilesley**, 38 Sylvia Ave Halifax NS  
**Elizabeth Sutherland**, 66 Rockingstone Rd Halifax NS  
**Grosvenor-Wentworth**, 4 Downing St Halifax NS  
**Hillside Park**, 15 Hillside Ave Lower Sackville NS

Ted Moore, Operations Manager  
Tel: (902) 464-2000 #4398, Fax: (902) 464-2201

**A mandatory bidders' site meeting is scheduled for *MONDAY, JULY 28<sup>TH</sup>, 9:00 A.M. COMMENCING AT PROSPECT ROAD MAIN ENTRANCE AND THEN CONTINUING TO J L ILSLEY, ELIZABTH SUTHERLAND, GROSVENOR-WENTWORTH AND HILLSIDE PARK.***

**To obtain documents:**

**Download tender documents in .pdf format from the School Board's Website: [www.hrsb.ns.ca](http://www.hrsb.ns.ca) "Quick Links/Ask About Tenders".**

*The Halifax Regional School Board encourages equity and affirmative action programs.*

# Table of Content

	<b>Page</b>
1.0 Instructions to Bidders .....	3
1.1 Conditions of Tender .....	4
1.2 Other Requirements .....	7
1.5 The Contract .....	11
2.0 Scope of Work .....	13
3.0 Contractor’s Information Sheet .....	23
3.3 Sub Contractor List .....	24
3.5 Schedule of Prices .....	26
3.7 Proposed Fixed Price .....	27

## **SAMPLE CONTRACT (DO NOT RETURN SAMPLE CONTRACT WITH BID DOCUMENTS)**

Schedule “A” Sample Agreement for Supply of Services .....	29
Appendix “A” Terms and Conditions .....	31
Appendix “B” Insurance and Risk .....	42
Appendix “C” Description of Service .....	48
Appendix “D” Undertaking to Comply & Safety Checklist .....	51

## **SAFETY PLAN/CONTRACTOR’S CHECK LIST**

Appendix “E” Project Safety Plan Outline .....	56
Appendix “F” Contractor’s Check List .....	61

## **NOTICE – CEASATION OF PUBLIC TENDER OPENINGS**

As of April 1, 2014 Public tender openings are no longer held for any tenders relating to goods, services or construction for HRSB. A list of bidders and bid amounts will be posted on the Procurement Services website (<http://novascotia.ca/tenders/tenders/ns-tenders.aspx>) shortly following the closing of the tender. All bid submissions are subject to evaluation after opening and before award of contract. The winning bidder and award amount will be posted on the Procurement Services website (<http://novascotia.ca/tenders/tenders/ns-tenders.aspx>) after evaluation.

1.0 **GENERAL**

The Halifax Regional School Board is seeking bids from qualified suppliers/contractors for a ***MOD BIT ROOF REPLACEMENTS PACKAGE #2 as per the plans and specifications prepared by FBM Architecture.***

1.1 **INSTRUCTIONS TO BIDDERS**

**TENDER  
SUBMISSION:**

- (a) Sealed Bids will be received by:

Halifax Regional School Board  
33 Spectacle Lake Drive  
Dartmouth, N.S.  
B3B 1X7

Until ***2:00:00 P.M., TUESDAY, AUGUST 5, 2014***, (as verified by the phone clock on the Commissionaire's desk at 33 Spectacle Lake Drive) for the following projects:

***TENDER #3694 MOD BIT ROOF REPLACEMENTS – PACKAGE #2***

***Should the School Board Office be closed for any reason the tender closing will be postponed to the next business day.***

- (b) Submit one copy of the original tender on the enclosed tender form. Each item on the form must be completed unless noted otherwise. Bids must be signed by an authorized representative of the Suppliers/Contractors. Incomplete bids will be rejected. Bids must be submitted on or before the advertised time and date in a sealed envelope clearly marked:

***TENDER #3694 MOD BIT ROOF REPLACEMENTS – PACKAGE #2***

- (c) It is the responsibility of the bidder to ensure their submissions are received on time. Faxed bids will not be accepted.

- (d) Addenda must be issued by the Board no less than three (3) business days before tender closing. Addenda cover letters shall be signed and attached to the tender documents.

1.2 **CONDITIONS OF TENDER**

- (a) No term or condition shall be implied, based upon any industry or trade practice or custom or in a practice or policy of the Board or otherwise, which is inconsistent or conflicts with the provisions contained in these instructions.
- (b) Any changes to this tender or specifications shall be stated by the Board in writing. All correspondence, inquiries, instructions, etc. in connection with the work shall be made through the office of the Halifax Regional School Board, c/o Manager of Accounting & Purchasing or representative.
- (c) Tender price must include freight, duty, and all taxes, rates and charges, which are applicable at the time the contract is awarded. It is the responsibility of the bidder to find out from the appropriate authorities what taxes, rates and charges are applicable to this tender.
- (d) The Contractor is responsible for obtaining all provincial, municipal and other permits as required for the work, and shall adhere to all regulations from regulatory bodies, including the National Building Code, 2005. They shall pay all fees for these permits. Sub-trades are responsible for obtaining permits and following regulations as they affect their work.
- (e) Invoices shall be submitted to: Halifax Regional School Board  
c/o Operations Services Coordinator-Maintenance  
33 Spectacle Lake Drive,  
Dartmouth, NS B3B 1X7

Contact information to be supplied to the successful bidder as part of the award confirmation.

Payment: Payment terms will be considered as Net 30 days from date of invoice.

- (f) Bidders or their employees must not be employees of the Halifax Regional School Board.
- (g) The bidder must comply with Nova Scotia Fire Safety Act and all Municipal Regulations, Ordinances and other laws including the Occupational Health and Safety Act.
- (h) Persons or firms submitting tenders shall be actually engaged in the line of work required by the specifications.
- (i) When applicable, a bidder shall list, in the space provided in Section 3.3, the names of the sub-contractors they propose to use with each sub-contractor's tender price. A change in sub-contractors from this list will require permission in writing from the Board.
- (j) Except as the specifications may be modified by Addenda, the successful



contractor will be held to furnish under this tender all work as specified.

- (k) The contractor shall save, defend, and indemnify the Halifax Regional School Board against all costs which the School Board may sustain or incur by reason of any act or omission of the contractor or its' agents or sub contractors.
- (l) Property loss and/or damage that occurs during the course of work or caused by negligence on the contractors part during the course of the work shall be reported by HRSB Operations Services to the School Insurance Program (SIP) office. Adjusters may be assigned to manage restoration of damaged, defaced or stolen HRSB property. HRSB and/or its insurer reserve the right to assign management of restoration to the adjuster. The contractor shall be responsible for all costs to repair or replace any School Board property, which has been damaged, defaced or stolen during the course of work.
- (m) The term of the contract will be from date of award to ***OCTOBER 31, 2014***.
- (n) Where the Tender Documents stipulate a particular product, written requests for substitutes will be considered by the Board up to five (5) business days prior to the tender closing date. Such requests shall be accompanied by complete descriptive and technical information including MSDS so that a proper evaluation can be made.

When a request for approval of a product is made, the Board may grant approval and will attempt to issue an Addendum to this effect to known bidders. However, HRSB assumes no liability for the delivery of electronic transmissions.

All products used in the course of this work are to be used, stored, and maintained as per the instructions written on the MSDS sheet.

- (o) Time and Material costs must be provided as listed in Section 3.6
- (p) **Unique Logistics**  
Completely describe how your Tender will respond to the unique logistics of each school or administrative site as set out in the Project Scope and fully describe, in the same manner, all items of equipment, service, and support you will provide to respond to those logistics and all pricing and other matters relating to them.
- (q) **HRSB Discretion**  
The Bidder hereby acknowledges that:
  - a) HRSB shall have the right to reject any or all Tenders for any reason, or to accept any tender which HRSB in its sole, unrestricted discretion deems most advantageous to it. The lowest, or any, Tender will not necessarily be accepted and HRSB shall have the unrestricted right to:
    - i) accept any Tender, and in the event it only receives informal, non-conforming or qualified Tenders with respect to this Tender, accept any such Tender; or

- ii) Accept a Tender that is not the lowest price;
  - iii) Reject a Tender that is the lowest price even if it is the only tender received;
  - iv) Reject any Tender that contains any irregularities, informalities, conditions or qualifications;
  - v) Reject any Tender that is not accompanied by the required tender security documents;
  - vi) Reject any Tender that is not properly signed by or on behalf of the Bidder;
  - vii) Reject any Tender that contains an alteration in a quote that is not initialed by or on behalf of the Bidder;
  - viii) Reject any Tender that is incomplete or ambiguous; or
  - ix) Reject any Tender that does not strictly comply with other requirements contained in these instructions.
- b) HRSB reserves the right to consider, during the evaluation of Tenders:
- i) Information provided in the Tender itself;
  - ii) Information received in response to enquiries of credit and industry references set out in the Tender;
  - iii) The manner in which the Bidder provides services to others;
  - iv) The experience and qualification of the Bidder;
  - v) The compliance of the Bidder to HRSB's requirements and specifications;
  - vi) Such alternate goods, services, terms or conditions that may be offered, whether such offer is contained in a Tender or otherwise,
  - vii) Splitting the Tender and Project Scope into multiple parts and accepting Tenders (or portions thereof) from more than one Bidder;
  - viii) Rejecting Bidder's recommendation of a Subcontractor or any other third party associated with the Tender and jointly along with the Bidder, determine alternate acceptable third parties; and
  - ix) Any other consideration in HRSB's discretion;
- c) HRSB may rely upon the criteria it deems relevant, even if such criteria has not been disclosed to Bidder. By submitting a Tender, the Bidder acknowledges the HRSB's rights under this Section and absolutely waives any right or cause of action against HRSB and its employees, agents or Trustees by reason of HRSB's failure to accept the Tender submitted by the Bidder, whether such right or cause of action arises in contract, tort including negligence or otherwise; and
- d) HRSB shall not at any time have any obligation to deal exclusively with the Bidder. HRSB expressly reserves its rights, in its sole discretion, to seek a Tender regarding the subject matter hereof, from any person whomsoever

and at any time.

(r) **Limitation of Liability**

Bidder, by submitting a bid to this Tender, agrees that it will not claim damages, costs or expenses for whatever reason, relating in any way to this Tender and any resulting process (including without limitation any subsequent discussions or negotiations, if any, or in respect of any competitive process) and waives any and all claims against HRSB whatsoever, whether for costs, damages or expenses incurred by Bidder in preparing its Tender, in participating in this tender process (including without limitation any subsequent discussion or negotiation, if any), loss of anticipated profit or any other matter whatsoever related to this tender and any resulting process, discussions or negotiations.

(s) **Construction Contract Guidelines**

The Halifax Regional School Board acknowledges and complies with the **Nova Scotia Transportation and Public Works Construction Contract Guidelines.**

1.3 **OTHER REQUIREMENTS**

- (a) The bidder must provide with the submitted tender document a certificate indicating the completion of the Nova Scotia Construction Safety Association's Construction Safety Program or other WCB approved safety audit company that jointly sign the Certificate of Recognition with the WCB.
- (b) The bidder must provide with the submitted tender document a letter showing they are in good standing with the Worker's Compensation Board.
- (c) The bidder must provide with the submitted tender document a tentative schedule indicating timelines for completion of works. **Upon award of work, the successful bidder shall provide within three (3) business days a schedule clearly indicating timelines for completion of all aspects of the project. Shop drawings/samples must be returned to HRSB for Consultant's review within five (5) days upon award.**
- (d) The bidder must provide with the submitted tender document, an insurance certificate showing **HRSB as "ADDITIONAL INSURED"** with proof of:
- (i) Commercial General Liability insurance, including but not limited to, products liability and completed operations, contractual liability, owners and contractors liability, attached machinery extensions, endorsement, independent contractor, for a combined single limit of no less than **\$5,000,000** per occurrence; Builder's Risk Insurance in the amount of the Contract Price.
  - (ii) Commercial Auto Liability insurance covering all owned, non-owned and hired vehicles for a minimum combined single limit of **\$2,000,000** per occurrence; and
  - (iii) It is also agreed that the above insurance coverage is primary.

Upon award, the bidder shall secure and maintain the insurance as noted above at its expense during the term of the contract.

The Halifax Regional School Board must be named as additional named insurance

pertaining to the work for this project. Furthermore, Halifax Regional School Board must receive at least thirty (30) days notice of cancellation or modification of the above insurance. Bidders shall at all times keep in force insurance as may be required.

(e) **BID SECURITY**

The bidder **MUST** provide with the submitted tender document **Bid Security** in the amount of **ten percent (10%) of the Contract Price** (before HST) in the form of a Certified Cheque, Irrevocable Standby Letter of Credit or Bid Bond payable to, or naming the Halifax Regional School Board.

**BID BONDS *must be provided by a surety company licensed to issue surety bonds in the Province of Nova Scotia:***

- Provide bond on the standard CCDC Bid Bond Form, latest version, in the amount of not less than **ten percent (10%) of the Contract Price (before HST)**.
- Bid Bonds, submitted by the general contractor bidder, signed and sealed by the principal (Contractor) and Surety and shall be with an established Surety Company satisfactory to and approved by the Halifax Regional School Board.
- Where a Bid Bond is used as Bid Security, include the cost of providing the Bid Bond in the Tender Contract price.

Where **CERTIFIED CHEQUE or BANK DRAFT** is provided as bid security:

- Provide a certified cheque or bank draft, endorsed in the name of the Halifax Regional School Board, for a **sum not less than ten percent (10%) of the amount of the Contract Price (before HST)**.
- Where certified cheque or bank draft is used as Bid Security, include the cost in the Contract price.

Where the **IRREVOCABLE STANDBY LETTER OF CREDIT** is used as bid security:

- Provide an Irrevocable Standby Letter, endorsed in the name of the Halifax Regional School Board, for a sum not less than **ten percent (10%) of the Contract Price (before HST)**.
- The Irrevocable Standby Letter of Credit shall be issued by a certified financial institution subject to the Uniform Custom and Practices for Documentary Credit (1993 revision or latest revision) International Chamber of Commerce (Publication No. 500).
- Where Irrevocable Standby Letter of Credit is used as bid security, include the cost in the Tender Contract Price.

**RETURN OF BID SECURITY:**

- The bid security of the unsuccessful bidders will be returned to them after the contract has been signed, or previous to such time, at the discretion of the Halifax Regional School Board. The above shall apply provided a contract is awarded within sixty (60) days from the closing date of the bid. If no contract is awarded, all bid security will be returned.

(f) **CONTRACT SECURITY (ONLY REQUIRED FOR BIDS OVER \$100,000)**

For bids over \$100,000 bidders must provide **Contract Security by a surety company licensed to issue surety bonds in the Province of Nova Scotia** in the form of one of the following:

- Letter of Surety.
- Performance Bond and a Labour and Material Payment Bond OR
- Certified Cheque or Bank Draft OR Irrevocable Letter of Credit bearing the bidder's original signature, payable to or naming the Halifax Regional School Board as insured.

Bidder shall maintain performance assurance in force for a period of not less than twelve (12) months after the issue of the substantial performance certificate certified by Halifax Regional School Board and until completion of the contract.

Should it become apparent that the final cost of the project will **exceed the total amount payable by more than 10%**, the bidder shall arrange to have their bonds reissued based on the projected final cost.

Where a **LETTER OF SURETY** was used as **CONTRACT SECURITY**:

- Within ten (10) days after notification of award of the Contract, provide a Performance Bond and a Labour & Material Payment Bonds each in an amount **equal to fifty percent (50%) of the Contract Price (before HST)**, naming the Halifax Regional School Board.
- Performance Bond and Labour and Material Payment Bonds, submitted by the bidders, shall be provided at the expense of the bidder and shall be with an established Surety Company satisfactory to and approved by the Halifax Regional School Board.
- Include the cost of providing the Performance Bond and Labour and Material bond in the Contract price.

Where a **CERTIFIED CHEQUE OR BANK DRAFT** is used as **CONTRACT SECURITY**:

- The Certified Cheque or Bank Draft submitted during the bid period will be cashed and the amount retained by the Halifax Regional School Board shall serve as Performance Assurance, including the payment of all obligations arising under the Contract.
- The Certified Cheque or Bank Draft will be held in lieu of the Performance Bond and Labour and Material Bonds, providing that, at Contract award, the successful Bidder shall supplement their Certified Cheque or Bank Draft to maintain an amount of **twenty (20%) of the Contract price** (before HST) under the contract.
- The amount remaining will be returned without interest after a period of not less than twelve (12) months after the issue of the substantial performance certificate

certified by the Halifax Regional School Board and shall serve as performance assurance until completion of the contract.

- Where certified cheque or bank draft is used as Performance Assurance, include the cost of providing the certified cheque in the Contract price.

Where **an IRREVOCABLE STANDBY LETTER OF CREDIT** is used as **CONTRACT SECURITY**:

- The Irrevocable Standby Letter of Credit for a sum not less than **ten percent (10%) of the Contract price (before HST)** submitted during the bid period will be retained by the Halifax Regional School Board and shall serve as performance assurance, including the payment of all obligations arising under the contract. The irrevocable standby letter of credit shall be issued by a certified financial institution subject to the Uniform Customs and Practices for Documentary Credit (1993 revision) International Chamber of Commerce (Publication No. 500).
  - Where irrevocable standby letter of credit is used as Performance Assurance, include the cost of providing and Irrevocable Standby Letter of Credit in the Contract Price. The contractor shall provide to the Halifax Regional School Board documentation throughout the duration of the contract that the irrevocable standby letter of credit remains in full effect at all times as specified.
  - Upon expiry of the Irrevocable Standby Letter of Credit, a separate Irrevocable Standby Letter of Credit shall be provided for work requiring extended warranties for such amounts as are required by the contract.
- (g) The bidder must provide with the submitted tender document a completed copy of Appendix “E” Safety Plan information sheet. The contractor prior to commencement of work must have a safety plan in place for use by the contractor personnel regarding potential hazards and work practices specific to the site.
- (h) ***HRSB is directly responsible for the safety of its students and staff. Should contractors be required to work in or on school property while children are present, it is a MANDATORY HRSB REQUIREMENT that contractors assign the work to employees and/or sub-contractors who DO NOT have a CRIMINAL RECORD and who ARE NOT LISTED ON THE CHILD ABUSE REGISTRY. By checking the “Agreed” box at the bottom of clause 3.4 below you are confirming that you understand and will abide by this mandatory HRSB requirement. Failure to comply with this requirement may result in immediate contract termination.***
- (i) Contractors must submit warranty information with the tender bid submission and successful bidders must submit all appropriate warranty documents with final payment invoice.
- (j) Bidders are advised that, as per the Halifax Regional School Board Tobacco Free Schools and Workplace Policy, the HRSB endorses and supports implementation of the Nova Scotia Smoke Free Places Act 2002, which prohibits tobacco possession for persons under the age of 19 and declares that no person shall smoke in schools, school board

offices or on school grounds.

#### 1.4 **AMENDMENTS OR WITHDRAWAL OF TENDER PRIOR TO BID CLOSING**

- (a) Tender may be amended or withdrawn **by post or facsimile (902) 464-0161 PRIOR** to Tender Closing date and time.
- (b) Clearly indicate on the fax transmission or submitted envelope, whether your correspondence is an amendment or withdrawal and the title of the Tender. Sign and seal as required for tender, and submit at address listed under closing location on the cover of this document.

#### 1.5 **THE CONTRACT**

##### **1.5.1 Binding Effect of Proposal and Contract Finalization**

The Bidder hereby acknowledges that its Tender constitutes a contract with HRSB, and the terms and conditions of this Tender and the bidder response (with the Tender taking precedence in the event of any inconsistency or conflict of terms) shall govern such agreement. Such contract shall remain binding upon Bidder until the earlier of:

- a) Written notice from HRSB that the Bidder's Tender is rejected as unsatisfactory; or
- b) Issuance by HRSB of its PO to the Bidder with respect to this Tender, pursuant to Section 1.2(p), and upon such issuance, the Bidder shall be regarded as the Contractor hereunder; or
- c) Execution of the Contract by both HRSB and the Bidder pursuant to Section 1.2(p); or
- d) Written notice from HRSB that it has entered a Contract with a Contractor and that the Bidder has been unsuccessful under this Tender.

##### **1.5.2 Contract Documents**

1.5.2.1 The attached form of contract (Schedule A) is a version that shall be issued to or executed by the successful bidder pursuant to the terms and conditions of this Tender. It is NOT TO BE executed and returned by the bidder as part of its (proposal or Tender response).

1.5.2.2 After the contract has been awarded and signed, the contractor will be contacted by the appropriate Regional Manager to attend a site visit to complete Appendix D of the contract – 'Undertaking to Comply and Contractors Safety Checklist' prior to the commencement of any work.

1.5.2.3 The Contract the Contractor will have with the HRSB, if awarded, will include:

- a) Such further documentation as may be negotiated and executed by the HRSB and the Contractor pursuant to Section 1.2(p); and

- b) This Tender and all of its Schedules, including without limitation any PO issued by HRSB to the Contractor, and any revisions, amendments or additional documents made thereto, if any; and
- c) The Tender, in its entirety and all promises made in the tender will be deemed covenants in the Contract and all information, representations and warranties made in the Tender will be deemed terms, representations and warranties of the Contract surviving the signing or issuance by HRSB of any additional or formal documents prepared by the HRSB.

1.5.2.4 For the purposes of evaluation and interpretation of Tenders, in the case of conflicts, discrepancies, errors or omissions between this Tender and any documentation issued or executed pursuant to Section 1.5.1, and the Tender, this Tender and such documentation shall take precedence over the Bidder response.

## **1.6 Your Contractual Terms**

- 1.6.1 List separately any contractual terms which must be included as part of the Contract if awarded to you and which would be a condition to HRSB's acceptance of your bid.
- 1.6.2 List separately any contractual terms which you would like the HRSB to consider but which would not be a condition to the acceptance by the HRSB of your bid and which would only be part of the Contract with the HRSB with the specific further agreement of the HRSB.



## **2.0 SCOPE OF WORK**

(a) Locations:

Prospect Road Elementary  
J L Ilsley Jr High  
Hillside Park  
Grosvenor-Wentworth  
Elizabeth Sutherland

PACKAGE #2 – MOD BIT ROOF REPLACEMENTS as per drawings and specifications prepared by FBM ARCHITECTURE.

- (b) School/Work site access control: **Contractor's employees shall always report to the main office of a school, indicate who they are and state their purpose on site prior to starting any work in the school.** Contractor is not permitted to work on the school site without HRSB assigned representative on site unless authorized by HRSB Manager of Operations.

The outside work area shall be appropriately demarked and/or surrounded by a barrier to prevent unauthorized entry to the work area. All workers shall contain their activity to the work site area. The contractor shall only use the school staff designated washroom and lunchroom facilities. Access to the school shall only be allowed as planned in coordination with HRSB Operations and the school administration.

The contractor and sub-contractor employees shall maintain professional and courteous behaviour, including work and communications practices, at all times on the project site. Communications and work shall be conducted so as to minimize the effect on regular school occupants and their activities.

- (c) Project/Safety Coordination: The contractor shall provide to HRSB within one week of award of contract a fixed schedule for all aspects of completion of work. The safety plan outline provided with this document must be posted on site during the execution of work and will be accessible to all workers on the site.

Where applicable, a **hot work permit** will be required to be completed prior to commencement of work and all conditions of the permit must be maintained until completion of hot work. A copy of the hot work permit signed by the contractor representative shall be provided to HRSB upon completion of each hot work session. Contractor must assign a designated fire watch as noted on the permit document who shall remain on site for three hours after completion of each hot work session.

The contractor will provide access to the work site and safety plan for inspection by HRSB Operations Services administration, HRSB health and safety Manager, consultants, regulatory inspectors as may occur throughout the duration of the project.

All necessary project coordination communications between project personnel and HRSB or site administration shall be from the project foreman/supervisor through the school

principal and/or the Manager of Operations.

- (d) Hours of work - All work shall be carried out during **regular working hours** unless otherwise indicated in writing by the Manager of Operations Services or a designate. Hours of work shall comply with local ordinances and bylaws for each site.
- (e) Site Material Control: The contractor shall be responsible for storage of all materials required to complete the renovation. The school shall not be used for storage of materials unless otherwise approved by the principal and manager of Operations Services. Any requirement for modifications to the building in order to allow delivery and installation of the new equipment is the responsibility of the contractor.

The contractor is responsible for security of all project materials and access to the project site and/or the school through the project site at all times until completion of work and acceptance of the finished project by HRSB. Such additional security costs for security personnel or other means of security as deemed necessary by the contractor will be the sole responsibility of the contractor.

The contractor shall keep the work site free from accumulated debris caused by the employees or work and shall remove all debris at the end of each work shift. Debris shall not be deposited in HRSB controlled garbage and/or recycling containers.

All waste materials and debris created during demolition and/or construction shall be disposed of in a dumpster provided by the contractor, to be removed at the end of the construction project, using a methodology that is in compliance with the applicable HRM solid waste by laws. Otherwise, the material must be removed and disposed of off site at the end of each working day. The waste materials may not be stored on site unless they are held in an approved project dumpster.

All temporary structures such as portable washroom facilities, materials storage trailer, work trailer, debris dumpster, vehicles, etc., shall be located a minimum of (25) twenty-five feet from the school building.

- (f) 1 Contractor is advised that the building will be occupied when work on this project takes place. Contractor to verify all areas of construction are secured and air tight partitioned to ensure that the health and safety of the students and staff are maintained during the construction period.
- 2 **Temporary Construction Utilities & Closures:**  
Contractor to erect and maintain 'dust-tight' barriers as noted. Prior to start-up, the 'dust-tight' separations must be in place as noted and reviewed by HRSB Project Manager and the Consultant. 'Dust-tight' enclosure will be reviewed during the course of construction. Contractor must maintain the current lighting levels, heating and ventilation standards in place.
- 3 **Interior Closures and Construction Areas:**
  - 3.1 For interior/interior locations provide the following:
    - 3.1.1 Gypsum board both sides to 9'-4", AFF.
    - 3.1.2 3 5/8 metal stud at 16" o.c., extend every 4<sup>th</sup> stud to underside of OWSJ.

- 3.1.3 Provide 10ml poly from top of gypsum board to u/s deck, sealed at the top of the wall to underside of deck.
- 3.1.4 Provide negative pressure within the construction space exhausted to the exterior.
- 3.2 Tarps are not to be used in lieu of the described closures.
- 3.3 Construction Access & Storage:
  - 3.3.1 Proper access to the area and storage of materials to be provided by the owner.
  - 3.3.2 Location to be determined by Project Manager on site.
- 3.4 Provide and maintain fire protection equipment during performance of the work as required by insurance companies, authorities having jurisdiction and governing codes, regulations and by-laws. Ensure no access is blocked for this purpose.
- 3.5 Contractor to coordinate a staging area for the Subcontractors for equipment, tools and material storage. Locate trailers and/or lockable waterproof sheds on site as per HRSB Project Manager's instructions.
- 3.6 Provide sanitary facilities in accordance with local authority having jurisdiction.

#### **4 Indoor Environmental Protection:**

- 4.1 There are several sources of potential contamination during a construction/renovation project. These include:
  - 4.1.1 Demolition Activities:
    - 4.1.1.1 Demolition activities release dust and fibrous materials into the air. Asbestos control is essential. Insulation in ceilings and walls, and ceiling tile all have a high fiber content that may produce substantial fibrous materials during demolition. Total suspended particulate levels may be very high with a significant portion of the total being of the respirable particle sizes.
- 4.2 Construction:
  - 4.2.1 Construction introduces additional dust and fibrous materials. Many construction materials used today emit a range of volatile organic compounds, especially formaldehyde. All glues, vapours, and gases rise from solvents used to prepare surfaces for bonding, and emissions from welding and soldering can introduce a range of metals into the air.
- 4.3 Finish Work and Materials:
  - 4.3.1 Final finishing and decorating of the renovated spaces can introduce strong odours and more VOCs. Solvents, paints and varnishes, and adhesives and other glues all add to the accumulation of these irritating compounds.
- 4.4 The Contractor shall ensure site clean up is carried out at the end of each working day. This includes partially used containers of solvents, paints, caulking, adhesives, and ensuring that these are removed from the site. All construction debris shall be removed from the site at the end of each day, either to an approved dumpster outside the building, or removed completely from the property.

#### **5 Preparation:**

- 5.1 Inspect perimeter partitions of the construction area, above the ceiling and seal all penetrations above and below the ceiling. Carefully remove the minimum number of ceiling tiles necessary to perform the inspection and the work of sealing the

partitions. HEPA vacuum above remaining ceiling tiles and grid and above existing ductwork to remove loose dust prior to removal.

- 5.2 Install new temporary 'dust tight' walls and include details of the plans for location.
- 5.3 Seal all doors leading to construction areas.
- 5.4 Any existing perimeter partitions of the construction area that do not extend to the underside of deck, Contractor to extend to ensure dust-free light area between the construction area and the remainder of the school.
- 5.5 Before any construction begins, doors between the rooms where work is being carried out and the adjacent corridor must be carefully sealed. Seal the doors completely at top, bottom, and sides. All vents, ducts, openings, etc. to be sealed. Do periodic inspections to ensure seals remain tight. Provide written information to the Project Manager.
- 5.6 Negative Pressure: Implement a system that extracts air directly from the work area, and discharges this air directly outside the work area to the outside of the building. All exhausted air is to pass through a HEPA filtering system before discharge to exterior. Place negative air pressure units in the area to be constructed in order to maintain a continuous negative pressure within the construction space. The construction area MUST be kept at a negative pressure relative to the occupied spaces.

## **6 During Construction:**

- 6.1 Erect impermeable dust barriers to completely seal off the work area from adjacent areas.
- 6.2 Dust barriers are to be maintained and remain in place until work is completed and the facility representative has approved removal. Any damage to barriers must be repaired as soon as possible.
- 6.3 **Contractors will be held responsible for any damage, dirt or dust migration beyond the construction enclosure and all cleaning cost to rectify same will be borne by the General Contractor.**
- 6.4 Post signs on the doors indicating that there is to be absolutely no unauthorized entrance or exit through the sealed-off areas except for fire or security reasons. Ensure that the construction crew and others comply with these restrictions.
- 6.5 Clean the construction area daily.
- 6.6 Dirty or dusty footprints outside the construction area that have been left behind by people who were in the construction area are to be promptly cleaned.
- 6.7 Use water mist and commercial dust suppressing products, approved by the Owner, to control dust. Execute work by methods to minimize raising dust from construction operations.
- 6.8 In the event equipment or materials cannot be removed from the construction area, use drop sheets to cover these items.
- 6.9 Debris transported from the second floor will be by the exterior in all cases possible. Contractor to provide sealed chute to covered bins below.
- 6.10 Failure to provide adequate dust control will result in the contractor bearing the cost of any clean up, repair or replacement deemed necessary as a result of dust generated from the project.

- 6.11 Ensure that windows, doors, penetrations, electrical outlets and intake and exhaust vents are properly sealed with plastic and taped within work area.
- 6.12 For exterior work adjacent to windows in an existing facility, test window openings for air tightness and seal windows that leak.
- 6.13 Verify that all fresh air intakes facing construction operation are shut down, and sealed not to allow dust or debris intake.
- 6.14 Ventilation:
  - 6.14.1 Seal duct openings in work area until completed.
  - 6.14.2 Maintain negative pressure between work area and adjacent occupied areas by using portable ventilation equipment.
  - 6.14.3 Verify that air is exhausted directly outside and away from intake vents, or filtered through a HEPA filter before being recirculated. Where odour is a concern, ensure an approved air scrubbing material is utilized.
  - 6.14.4 The main building's air handling system shall be disconnected from use in areas of construction. This will require sealing of existing duct work on both the supply and return air systems.
- 6.15 Remedial Measures:
  - 6.15.1 Water leaks and flooding shall be reported immediately to the Project Manager.
  - 6.15.2 Detected water damage must be thoroughly investigated in consultation with the Project Manager. A plan of action will then be implemented as approved by the Project Manager.
  - 6.15.3 All investigations, removal and abatement procedures shall be conducted in a manner that does not promote dispersal of dust and spores.
- 6.16 Cleaning During Progress of Work:
  - 6.16.1 Clean work area with HEPA filter-equipped vacuums and wet mops, or both, at end of each work shift and as necessary.
  - 6.16.2 Ensure ventilation system is functioning properly and is cleaned if contaminated by soil or dust after work is complete.

## **7 After Construction:**

- 7.1 Clean work area with HEPA filter equipped vacuums and wet mop.
- 7.2 Ensure air vents and ductwork are cleaned and seals removed.
- 7.3 If required, Contractor to conduct final indoor air quality test. Submit test results to the HRSB Project Manager.

## **8 Cutting and Patching**

- 8.1 Provide openings larger than 8" in diameter in non-structural elements of Work for penetrations of structural, mechanical and electrical Work. Openings smaller than 8" diameter will be provided by the Sub-trades requiring same.
- 8.2 When floor cutting is required, Contractor to confirm there are no under-floor electrical or junction boxes. Contractor must utilize a electrically power operated floor saw.
- 8.3 Fit work airtight to pipes, sleeves, ducts, conduit, and after penetrations through surfaces.
- 8.4 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with approved fire-stopping and smoke sealing materials, full thickness of the construction element, as required to maintain the required fire resistance and smoke spread rating.

- 8.5 Refinish surfaces to match adjacent finishes: For continuous surfaces refinish to nearest intersection; for an assembly, refinish entire unit.
- 8.6 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

**9 Progressive Cleanliness & Restoration of Damage**

- 9.1 Maintain Work daily in tidy condition, free from accumulation of waste products and debris. Remove waste material and debris from site at end of each working day, and dispose of off-site. Ensure permits are obtained from authorities having jurisdiction for disposal of waste and debris.
- 9.2 Provide on-site containers for collection of waste materials and debris, and provide clearly marked separate bins for recycling.

**10 Close Out Procedures:**

- 10.1 Remove dust, stains, paint spots, soil grease, fingerprints and accumulations of construction materials, interior and exterior to the building. Perform cleaning in accordance with installer's instructions for each material. Final cleaning shall include:
  - 10.1.1 Washing exterior paved surfaces disturbed under this contract.
  - 10.1.2 Cleaning and polishing of glass and finish metals, interior of areas noted.
  - 10.1.3 Cleaning of hardware, mechanical fixtures, lighting fixtures, cover plates and equipment, including polishing of their finish metal, porcelain, vitreous and glass components.
  - 10.4.4 Removing of visible manufacturer's labels left on materials, components and equipment.
  - 10.5.5 Cleaning of new flooring and of all other flooring disturbed under this contract.

**10.2 Maintenance materials:**

- 10.2.1 Maintenance materials provided shall be new, not damaged or defective, and of the same quality and manufacture as products provided in the work. If requested, furnish evidence as to type, source and quality of products provided.
- 10.2.2 Provide 3% of all hard tile, floor and walls and 4 liters of each paint colour specified.

**10.3 Testing Balancing and Adjusting**

Provide testing and ensure agency is a current member of AABC certified to perform services.

**10.4 Demonstration of systems and equipment**

Provide complete demonstration of all systems and equipment in the presence of the Owner and maintenance representations at the following times:

**10.5 Submittals**

- 10.5.1 Provide with application for substantial completion certificate.
  - 10.5.1.1 Certificate of final inspection report from electrical utility or inspection.
  - 10.5.1.2 Other reports required or specified.
  - 10.5.1.3 Maintenance manuals and operating instructions.

10.5.2 Submit with application for release of final payment:

- 10.5.2.1 Final project record drawings including shop drawings.
- 10.5.2.2 Performance bonds which shall remain in effect for one year after takeover date.
- 10.5.2.3 Completed Liability Insurance Policy extended for one year over date.
- 10.5.2.4 Written guarantee covering all workmanship and materials used in the work.
- 10.5.2.5 Certificate from Worker's Compensation Board.
- 10.5.2.6 Maintenance Bonds as specified.
- 10.5.2.7 Maintenance Manual.
- 10.5.2.8 Spare parts and maintenance materials and list.
- 10.5.2.9 Extended warranties.

**10.6 Substantial performance and final inspection procedures:**

10.6.1 Provide:

An inspection of the work, identify deficiencies and defects; repair as required. Notify the consultants in writing and request Substantial Performance Final Inspection.

10.6.2 Present at the Substantial Performance Inspection will be:

10.6.2.1 The consultants and his sub-consultants that he requires and notifies.

10.6.2.2 The Owner and his consultants upon notification by the design builder.

10.6.2.3 The design builder and such sub-contractors that he considers are required.

10.6.3 The Contractor will compile a Substantial Performance deficiency list at this inspection and issue it to the Owner and his consultants.

10.6.4 Upon the Owner's completion of the deficiencies, the design builder shall submit an application for final payment and a certificate for payment will be issued by the consultant to the Board.

**10.7 Substantial performance:**

10.7.1 The owner will issue a Certificate of Substantial Performance when satisfied outstanding deficiencies noted during inspections prior to the Substantial Performance inspection have been corrected, and the work is substantially performed.

10.7.2 The owner reserves the right to occupy and use portions of the building(s), whether partially or entirely completed, or whether completed on schedule or not, provided such occupancy does not interfere with the Design Builders continuing work. Partial occupancy or installation by the Owner of his equipment shall not imply acceptance of Substantial Performance, in whole or in part, nor shall it imply acknowledgement that terms of the agreement are fulfilled.

10.7.3 The Certificate of Substantial Performance will be attached to the list of remaining deficiencies to be rectified before final acceptance.

10.7.4 Make submissions specified in this section.

**10.8 Completion certificate:**

- 10.8.1 The owner will issue a Certificate of Performance when he is satisfied that outstanding deficiencies noted during inspections have been corrected and the work is complete.
- 10.8.2 A list of remaining deficiencies to be rectified before final acceptance will be attached to the completion certificate.
- 10.8.3 Make submissions specified in this section.

**10.9 Warranties:**

- 10.9.1 Establishment of warranties:
  - 10.9.1.1 Warranties shall commence on date of approval of the Substantial Performance Certificate.
- 10.9.2 Warranty period:
  - 10.9.2.1 The Owner will notify the design builder of defects observed during warranty period and request him to remedy the defects in accordance with the contract documents.
  - 10.9.2.2 Thirty days before the expiration of warranties, the Owner and the design builder will inspect the work as arranged by the design builder noting defects of products and workmanship.
  - 10.9.2.3 The designer builder shall immediately remedy such noted defects.



## 2.1 **SITE VISITS**

- (a) Bidders will be deemed to have familiarized themselves with existing site and all other conditions which may affect performance of the Contract. No plea of ignorance of such conditions as a result of failure to make all necessary examinations and calculations will be accepted as a basis for any claims for extra compensation or an extension of time.
- (b) **A mandatory bidder's site meeting is scheduled as per the directions on the cover sheet of this document.**

## 3.0 **FORM OF TENDER - BIDDER DECLARES**

- (a) That this tender was made without collusion or fraud.
- (b) That the proposed work was carefully examined.
- (c) That the bidder is familiar with local conditions.
- (d) That contract documents and attachments were carefully examined.
- (e) That all the above were taken into consideration in preparation of this tender.

## 3.1 **BIDDER AGREES**

- (a) To enter into a contract to supply all labour, material and equipment and to do all work necessary to complete the Work as described and specified herein for the prices as per the Form of tender, Schedule of Prices, Article 3.5.
- (b) That this tender is valid for acceptance for 60 days from the time of tender Closing.
- (c) That failure to enter into a formal contract and give specified documents within time required will constitute grounds for forfeiture of this agreement.
- (d) That if Certified Cheque or bid bond is forfeited, the Owner will retain difference in money between amount of tender and amount for which owner legally contracts with another party to perform the work and will refund balance, if any, to bidder.
- (e) I/WE certify that the company listed herein is in good standing with the City of Halifax Tax Collector and all Municipal, Provincial and Federal Tax Agencies. Failure to complete this certification and maintain this status will be cause for rejection of your tender and/or cancellation of any contractual undertaking with the Board. We further agree with and accept the terms set out in this tender document.

*Halifax Regional School Board*

**CONTRACTOR INFORMATION SHEET**

***TENDER #3694  
ROOF REPLACEMENT  
PACKAGE #2***

FIRM \_\_\_\_\_

ADDRESS \_\_\_\_\_  
\_\_\_\_\_

E-MAIL ADDRESS \_\_\_\_\_

POSTAL CODE \_\_\_\_\_ PHONE \_\_\_\_\_ FAX \_\_\_\_\_

NAME OF PERSON SIGNING FOR FIRM \_\_\_\_\_

POSITION OF PERSON SIGNING FOR FIRM \_\_\_\_\_

The undersigned company represents and warrants that it is authorized to carry on business of this nature and that it is not prohibited by any law applicable in Nova Scotia from performing this Contract. The undersigned also acknowledges receipt and understanding of, and has taken into consideration all information presented in, this tender and agrees to be bound by its terms and conditions. The undersigned further confirms and agrees that the person whose name is set out below is fully authorized to represent the company and to bind it to this bid and the Contract awarded pursuant to it and in all matters relating to or arising out of the subject matter of this tender.

I/WE, the undersigned, having carefully examined the ***#3694 MOD BIT ROOF REPLACEMENTS – PACKAGE #2*** tender documents, and having read, understood, and accepted the Conditions of the tender which form part of the tender documents, hereby offer to provide the materials and service in strict accordance with the ***#3694 MOD BIT ROOF REPLACEMENTS –PACKAGE #2*** documents, which form part of this tender.

I/WE, hereby agree that notification of acceptance of this bid shall be in writing and may be sent by prepaid post or fax, and if sent by prepaid post, acceptance shall be deemed to have been made on the date of mailing of such notification.

3.2 **REFERENCES:**

The Bidder shall furnish particulars of at least three contracts successfully completed or currently being carried to completion. The projects quoted should preferably be approximate in nature to the Works now proposed for and be of comparable or greater size.

Contact Name & Phone #	Date	Contract Value
_____	from _____ to _____	_____
_____	from _____ to _____	_____
_____	from _____ to _____	_____
_____	from _____ to _____	_____

3.3 **SUB CONTRACTORS:**

The Bidder shall enter the name and address of each Sub-Contractor used in making up this Tender. Only one Sub-Contractor shall be named for each part of the work to be sublet.

Subcontractor/Suppliers/Manufacturers	Service/Material



3.5 **SCHEDULE OF PRICES**

**CONTINGENT UNIT PRICES:** [see article 1.2 (p)]

Provide unit prices for contingency items in the event that additional work items are required in association with the scope of work as outlined in section 2.0 and the total value of unit prices shall be included in the Total Fixed Cost price.

Item No.	Description	Unit of Measurement	Unit Price
1.	DRAIN SUPPLY/INSTALLATION	EACH	\$ _____
2.	_____	_____	\$ _____
3.	_____	_____	\$ _____
4.	_____	_____	\$ _____
5.	_____	_____	\$ _____

3.6 **TIME AND MATERIAL PRICES:**

Provide unit prices for time and material work if no fixed price is requested in association with the work as outlined herein.

Item No.	Description	Unit of Measurement	Estimated Quantity	Unit Price
1.	_____	_____	_____	\$ _____
2.	_____	_____	_____	\$ _____
3.	_____	_____	_____	\$ _____
4.	_____	_____	_____	\$ _____
5.	_____	_____	_____	\$ _____
6.	_____	_____	_____	\$ _____

3.7 **PROPOSED FIXED PRICE**

The fixed price shall be the full inclusive value of the work. The prices submitted shall be all-inclusive and shall include for all the general and special requirements to meet the specifications of the work, including any contingent costs.

<u>Description</u>	<u>Total Fixed Price</u>
<i>PROSPECT ROAD</i>	\$ _____
<i>J L ILSLEY</i>	\$ _____
<i>ELIZABETH SUTHERLAND</i>	\$ _____
<i>GROSVENOR-WENTWORTH</i>	\$ _____
<i>HILLSIDE PARK</i>	\$ _____
<i>SUBTOTAL FOR ALL SCHOOLS</i>	\$ <u>_____</u>
<i>HST (15% OF TOTAL PRICE)</i>	\$ _____
<i>TOTAL CONTRACT PRICE</i>	\$ <u>_____</u>

SUBSTANTIAL PERFORMANCE DATE: \_\_\_\_\_

BIDDERS HST REGISTRATION NO. \_\_\_\_\_

3.8 **SIGNATURE:**

SIGNED AND DELIVERED  
in the presence of:

**CONTRACTOR**

\_\_\_\_\_  
Company name

\_\_\_\_\_  
Witness

\_\_\_\_\_  
Signature of Signing Officer

\_\_\_\_\_  
Name and Title (printed)

**SCHEDULE A**

**AGREEMENT FOR SUPPLY OF SERVICES**

This Agreement made effective on the \_\_\_\_\_ day of \_\_\_\_\_ in the year 20

**For:**

**Project Name:**

**Location:**

**Tender #**

by and between:

**HALIFAX REGIONAL SCHOOL BOARD ("HRSB")**

and

**COMPANY NAME:**

**ADDRESS:**

**CITY:**

**PROV:**

**Postal Code:**

(the "Contractor")

**The parties agree as follows:**

1. Contractor shall provide to HRSB the services set forth in Appendix "C" – Description of Services, and accompanying Exhibits (which along with all other obligations of Contractor set forth in this Agreement shall constitute the "Services") in accordance with the terms of this Agreement.
2. This Agreement consists of the following parts (together, the "Agreement"), each of which shall be construed as an integral part of this Agreement:

**This signature page**

**Appendix "A" – General Terms and Conditions**

**Appendix "B" – Risk Management & Safety**

**Appendix "C" – Description of Services  
Exhibit A – RFP or Invitation to Tender**

**Exhibit B – Response to RFP or Tender**

**Appendix "D" – Undertaking to Comply Form and Contractor Safety  
Checklist**

**Appendix "E" – Safety Plan**

**Appendix "F" – Contractor Checklist**

The above Appendixes and Exhibits are intended to be complementary, and what is required by any one shall be as binding as if required by all.

3. Contractor confirms that it has read this Agreement before signing it.

4. The individual signing below for Contractor warrants by his/her signature hereon that he/she has authority to bind Contractor to this Agreement.

**HALIFAX REGIONAL SCHOOL BOARD**

**CONTRACTOR**

Signature: \_\_\_\_\_

Signature: \_\_\_\_\_

Name (print): Kathryn Burlton

Name (print): \_\_\_\_\_

Title (print): *Purchasing Manager*

Title (print): \_\_\_\_\_

Date: \_\_\_\_\_

Date: \_\_\_\_\_

**SAMPLE ONLY**

**CONTRACTOR'S ATTENTION IS SPECIFICALLY DRAWN TO THE APPENDIX "A" TERMS AND CONDITIONS GOVERNING THIS AGREEMENT. EXECUTING PARTIES' ATTENTION IS DRAWN TO APPENDIX "C" AND APPENDIX "C" TO BE INITIALED OR EXECUTED BY EACH PARTY IN ACKNOWLEDGMENT OF THE TERMS THEREIN.**



## APPENDIX "A"

### TERMS AND CONDITIONS

#### SERVICES

**Services:** Contractor shall provide the Services to HRSB in accordance with the terms of this Agreement, on the HRSB properties specified in Appendix "C" (the "**Description of Services**"). Except as may be otherwise expressly provided in Appendix "C", Contractor shall provide all the equipment, personnel, supplies, consumables, supervision and labour necessary to complete the Services in a good and workmanlike manner. No changes or modifications to the Services or otherwise to this Agreement shall be valid unless made in accordance with Article 5 of this Agreement. The Contractor shall employ a competent supervisor who shall be in attendance at the place of work at all times while Services are being performed.

**Term:** This Agreement shall commence upon and later expire upon the dates specified in Appendix "C" (such period being the "**Term**"), unless earlier terminated in accordance with the provisions of this Agreement. Should Contractor continue to provide, and HRSB continue to pay, for the Services beyond the Term, such provision of Services shall be deemed to be on a temporary basis only and terminable at any time by HRSB with or without cause, and the provisions of this Agreement shall apply in full force (save as to the termination provisions in Article 9) until such termination.

#### FINANCIAL TERMS, PAYMENT, LIENS

**Contract Price:** For and in consideration of the Contractor providing the Services in accordance with the terms of this Agreement, the HRSB agrees to pay to the Contractor the sum of

§

(*plus HST*) hereinafter referred to as the "**Contract Price**". Such Contract Price shall include any and all expenses Contractor may incur in the performance of the Services.

**Invoices:** The Contractor shall submit a single invoice to HRSB for all Services rendered under this Agreement unless Appendix "C" provides otherwise. Contractor's invoice shall indicate applicable sales and use taxes as separate amounts and indicate the net taxable value including all applicable discounts. HRSB shall not be obligated to pay any taxes to Contractor unless Contractor is registered with the applicable authorities and provides its registration number on the invoice. Contractor's invoice shall be in a form acceptable to HRSB and contain sufficient details to ascertain the scope of Services performed and, if requested, Contractor shall provide documentation in support of an invoice. If HRSB disputes any portion of the invoice, it shall pay such invoice less the disputed amount, subject to adjustment upon resolution of the dispute. Non-payment by HRSB of any amount in dispute shall not alleviate, diminish or modify in any respect Contractor's obligations to perform as required by and in accordance with this Agreement.

**Payment of Invoices:** Upon the HRSB certifying that the Services have been completed, the HRSB shall pay to the Contractor, thirty (30) calendar days from the date of such certification,

unless otherwise stipulated in Appendix "C", the full Contract Price due and payable hereunder, less any holdback required to be retained under the *Builder's Lien Act* of Nova Scotia (the "*Builder's Lien Act*"), other statutory obligation or as otherwise stipulated in Appendix "C", provided the Contractor has submitted the following:

a written statement from the supplier(s) of all materials used for the Services certifying that payment has been made in full for same or waivers of liens from such supplier(s) in due form;

a worker's wage statement containing all the information required by the HRSB pertaining to the Contractor's, and all of its subcontractors', workers. Such statement requires the name of the workers, hours worked, rate of pay, total wages received, and a signature from each worker certifying that they have received payment in full for all time worked on the job indicated on the form; and

certification that the statement is correct.

**Release of Holdbacks:** No holdback shall be paid to the Contractor until the Contractor has provided to the HRSB a statutory declaration in a form as set forth in Canadian Construction Documents Committee ("CCDC") Document 9A, together with evidence of compliance with the *Workers' Compensation Act*, and, if applicable, a copy of the Certificate of Title for the Lands, dated thirty (30) calendar days from the issuance of the Certificate of Substantial Performance (as defined in the *Builder's Lien Act*) of work by the Contractor, confirming that no liens have been placed against the Lands in association with Contractor's Services.

**Liens:** Contractor shall keep the Lands and all HRSB property free from any and all laborers', materialmen's and mechanics' liens and similar claims and encumbrances. To the fullest extent permitted by law, Contractor waives all rights to assert such liens against the Lands and all HRSB property. If Contractor fails to release and discharge any claim of lien of others against the Lands and HRSB property within FOUR (4) business days of receiving notice from HRSB, HRSB may at its option discharge or release the claim of lien, or otherwise deal with the lien claimant, and Contractor shall be liable to and shall pay HRSB any and all costs and expenses of HRSB in doing so, including all reasonable legal fees and expenses. Notwithstanding the foregoing, for the purpose of enforcing the terms of this Agreement, HRSB may apply for the following liens and rights when circumstances deem it necessary:

if the Contractor contracts for one or more jobs with HRSB, the HRSB shall have a lien on the Contract Price and extras on that job as well as on their other jobs with the HRSB;

the HRSB shall have a lien on the Contractor's equipment or supplies on any job; and

in the case of Contractor, without sufficient cause (in the opinion of the HRSB), suspending work on any job which continues for more than two (2) days, HRSB may take possession of any materials delivered to or for the Contractor on such job and use same, giving the Contractor credit for its value at not more than cost thereof to the Contractor, against any liability of the Contractor to the HRSB and may use any of the Contractor's equipment that was in use on any of the HRSB's premises until the completion of the unfinished work.

**Tax:** Contractor shall comply with all applicable tax laws, including but not limited to laws relating to: (i) the collection and remittance of HST; and (ii) the withholding of applicable taxes from those of its employees performing work under this Agreement. Contractor shall be liable for and shall indemnify HRSB in respect of any claims, penalties, interest or costs made or assessed against HRSB arising from Contractor's non-compliance with tax laws.

**Audit:** Contractor shall keep and maintain true and correct books, records and accounts with respect to the Services and any materials supplied in relation to the Services, along with invoices and monthly summaries, for a period of seven (7) years after Contractor ceases to provide the Services. Contractor shall, upon request of HRSB, make available and permit HRSB during such period to inspect, make copies of, and audit all such records. If there is any revision to charges as a result of an audit, within thirty (30) days of the audit Contractor shall pay to HRSB the full amount of any credit or HRSB shall pay to Contractor the full amount of any shortfall, as the case may be. The provisions of this Section shall survive the termination of this Agreement.

## **DUTIES OF THE CONTRACTOR**

**Sub-Contractors:** Contractor shall not subcontract the whole or any part of the Services without first receiving the written consent of HRSB, which consent may be withheld in HRSB's sole discretion. Where such consent is granted, Contractor shall not be released or relieved from any obligations or liabilities of Contractor under this Agreement nor shall HRSB be prevented from pursuing any legal or equitable remedies it may be entitled to against Contractor. Contractor shall remain liable and responsible to HRSB for the actions and omissions of any subcontractor and shall ensure that any subcontractor strictly adheres to all terms of this Agreement, including any safety requirements referred to in this Agreement. When requested by HRSB, Contractor shall provide HRSB with all details concerning any and all subcontracted work.

**Site Representative and Instructions:** The Contractor shall identify in the Undertaking to Comply attached in Appendix "D" to this Agreement, a job site representative to act on the Contractor's behalf. This representative shall have the authority to represent the Contractor with relation to taking instruction on behalf of Contractor and entering agreements or taking such other actions on matters related to this Agreement. HRSB shall identify in Appendix "C" Description of Services, or through subsequent notice to Contractor, its project manager, who has the authority to represent HRSB and instruct Contractor on matters related to this Agreement. If the Contractor representative is not on the job site at the time of a visit by HRSB's project manager, the orders of the HRSB project manager to any worker present shall be carried out. Contractor shall not seek direction from any person on matters related to this Agreement, other than from the HRSB project manager.

## **DELAYS**

**Delays:** If the Contractor is delayed in the performance of the Services, and such delay is outside the Contractor's direct control, then the schedule to perform the Services may be extended for such reasonable time as the HRSB may decide in consultation with the Contractor. No such extension shall operate to extend the Term of this Agreement. Weather is not considered a reason for delay. No extension shall be made for delay unless written notice of

delay is given to the HRSB not later than two (2) working days after the commencement of delay, providing however, that in the case of a continuing cause of delay only one notice of claim shall be necessary, and for only such period as approved by HRSB in writing, in its discretion.

**Delay by HRSB:** The HRSB will not, except by written notice to the Contractor, stop or delay the Services as a result of pending instructions or proposed changes in the Services.

**Adherence to Schedule:** If the Contractor is delayed in the performance of the Services by any cause within the Contractor's control, the Contractor shall at no cost to the HRSB take effective action to restore the Services to the original time schedule for their completion, whether or not such schedule is appended to this Agreement.

## CHANGES IN THE WORK

**Change Orders:** The HRSB, without invalidating this Agreement, may make changes in the Services with the Contract Price and Term being adjusted accordingly, by written notice of change (a "Change Order"). No changes in the Services shall proceed without a Change Order signed by the HRSB and no claim for a change in the Contract Price or change in the Term shall be valid unless so ordered and at the same time valued by the Contractor as provided in Section 5.2.

**Change Approvals:** When a change in the Services is proposed or required, the Contractor shall present to the HRSB for its approval the value of the change whether an extra charge or a credit. Changes submitted for approval are to be accompanied by a detailed breakdown of labour and materials, to which shall be added supervision, overhead and profit charges. Change charges submitted shall be calculated in the following manner:

for work done by the Contractor, add to the net direct cost not more than ten (10%) percent for overhead, profit, supervision and bonding costs; and

for work done by any subcontractor, add to the net direct cost, not more than FIVE (5%) percent for overhead and profit payable to the subcontractor, and add not more than FIVE (5%) percent to the subcontractor's amount for supervision of the subcontractor by the Contractor and for bonding costs.

The HRSB will satisfy itself as to the correctness of such claim and, when approved by the HRSB, a Change Order shall be issued to the Contractor amending the Contract Price and Term as appropriate.

## DEFECTIVE WORK & DISMISSAL OF WORKERS

**Defective Work:** Defective work is work that has been rejected by the HRSB as failing to conform to this Agreement. Contractor shall promptly correct defective work, as required to conform to this Agreement, with no change in Contract Price. If, in the HRSB's opinion, it is not expedient to correct defective work, the HRSB may deduct from the Contract Price the difference in value between the Services as performed and that required by this Agreement, the amount of which will be reasonably determined by the HRSB.

**Dismissal of Workers:** The Contractor shall, on the request of the HRSB, immediately dismiss from the job any person employed by the Contractor who may, in the opinion of the HRSB, be incompetent or for misconduct, and such persons shall not again be employed on the job without the prior written permission of the HRSB. Foul language will be considered as misconduct.

## **PRODUCT OPTIONS AND SUBSTITUTIONS**

**Product Selection:** Contractor may:

for any products specified by non-proprietary specification in Appendix "C", select any product of any manufacturer which meets the requirements of this Agreement.

for products specified by proprietary specification and accompanied by words indicating that substitutions will not be accepted in Appendix "C", select any product or manufacturer named. Substitutions are not permitted; and

except where substitutions are not permitted, when a product is specified by proprietary specification, other unnamed products will be accepted, subject to such substitutions being the same generic type, and capable of performing the same functions and meeting or exceeding the standards of quality and performance, as the named product. Substitutions shall not require revisions to this Agreement or a Change Order.

**Product Substitutions:** When making a substitution, the Contractor shall represent in writing that:

Contractor has investigated substitute products and/or manufacturer and has determined that the substituted product meets the criteria specified in Section 7.1 (c);

Contractor will make any changes to the Services necessitated by the substitution as required for the Services to be complete in all respects; and

Contractor waives all claims for additional costs and time caused by substitution, which may subsequently become apparent.

## **COMPLIANCE WITH LAWS, SAFETY AND PRIME CONTRACTOR**

**Compliance with Laws:** Contractor shall comply with, and shall ensure subcontractors comply with, all applicable federal, provincial, and municipal laws, regulations and by-laws and to all other applicable orders, rules and regulations of any authority having jurisdiction respecting the Services, including without restriction all applicable environmental legislation, employment standards codes and workers' compensation legislation or equivalent legislation. CONTRACTOR SHALL FURNISH HRSB WITH WRITTEN CONFIRMATION FROM THE APPLICABLE WORKERS' COMPENSATION AUTHORITIES, OR EQUIVALENT AUTHORITIES, THAT CONTRACTOR AND ANY SUBCONTRACTORS ARE IN GOOD STANDING WITH SUCH AUTHORITIES, AND NO CONTRACTOR INVOICE SHALL BE PAYABLE UNTIL SUCH CONFIRMATION IS RECEIVED.

**Safety:** Contractor shall comply with and shall ensure all of its agents, employees and subcontractors comply with all applicable fire, safety, health, and environmental laws and regulations, including all safety, health and environmental requirements pursuant to any government permit, license, or authorization. Contractor shall be solely responsible for ensuring the safety and health of its agents, employees and subcontractors and for ensuring that its activities do not compromise the safety of HRSB's operations.

**Occupational Health and Safety Legislation:** Contractor shall comply with all applicable provisions of the *Occupational Health and Safety Act* (Nova Scotia) (the "Act") regulations thereto. Contractor shall execute and provide to HRSB the Undertaking to Comply Form with attached Pre-Construction Meeting Contractor Safety Checklist attached as Appendix "D". Contractor shall also supply to HRSB a Certificate of Recognition (COR) form as required under the Act and other applicable legislation.

**Designation of Prime Contractor:** The parties agree to designate in Appendix "D" that the Contractor shall be the "prime contractor" for the work site on the Lands for the purposes of the Act, during the Term, under this Agreement. The Contractor hereby agrees that:

such obligation shall extend to protect all contractors, employees, workers and persons as specified in the Act concerning the work site notwithstanding that they have been retained by HRSB after the date of execution of Appendix "D" by the Contractor; and

HRSB may in it's sole discretion notify the Contractor in writing that the Contractor shall, following the date of such notice, assume the role of the "prime contractor" under the Act with respect to the work site notwithstanding that the Contractor was not so designated in Appendix "D" at the time of it's execution by the Contractor, and the Contractor hereby agrees to do so.

**Responsibilities of the Prime Contractor:** Contractor shall:

direct all subcontractors, other contractors, employers, workers and any other personnel at the work site on safety related matters, to the extent required to fulfill its "prime contractor" responsibilities pursuant to the Act, regardless of:

whether or not any contractual relationship exists between the Contractor and any of these entities, or

whether or not such entities have been specifically identified in this Agreement;

ensure all obligations under the Act are strictly adhered to by all personnel;

be diligent in ensuring that its subcontracts comply with all health, safety and environmental legislation;

take appropriate disciplinary action against subcontractors who contravene health, safety or environmental legislation, which includes but is not limited to the suspending of the work performed by the subcontractors, before allowing them to continue to work on the site; and

ensure that Contractor or subcontractors never place the HRSB students, staff, volunteers or the general public at risk of injury or illness related to work conducted under this Agreement.

The HRSB shall provide Contractor, where applicable, with a list of all subcontractors under contract to the HRSB, working on the work site at the same time as Contractor, as well as their contact information. Failure by the HRSB to provide such information to Contractor shall not relieve Contractor of its obligation under this Section 8.5.

**HRSB Access:** At all times during the Term, HRSB Project Managers, agents and designates shall have the right to access, ingress and egress any work site, building or facility where Contractor performs the Services, and any part thereof, for any purpose, and neither Contractor nor its subcontractors shall refuse such access, ingress or egress whatsoever.

## TERMINATION

**Insolvency:** If the Contractor should be adjudged bankrupt, or makes a general assignment for the benefit of creditors because of insolvency or if a receiver is appointed, the HRSB may, without prejudice to any other right or remedy it may have, by giving the Contractor or receiver or trustee in bankruptcy written notice, immediately terminate this Agreement.

**Breach by Contractor:** If the Contractor should neglect to prosecute the Services properly or otherwise fail to comply with the requirements of this Agreement, the HRSB may notify the Contractor in writing that it is in default of its obligations and instruct it to correct such default within FOUR (4) business days immediately following the receipt of such notice. If the correction of the default cannot be completed in the FOUR (4) business days specified, the Contractor will be considered to be actually attempting to cure the default if it:

commences the correction of the default on a best efforts basis, in HRSB's sole opinion, within FOUR (4) business days of receiving a notice of default;

provides the HRSB with a schedule for such correction which HRSB approves by written notice to Contractor; and

completes the correction in accordance with such approved schedule and without any additional cost or delay to the HRSB.

If the Contractor fails to correct the default in the time specified or subsequently agreed upon, the HRSB, without prejudice to any other right or remedy it may have, may terminate the Contractor's right to continue with the Services in whole or in part, and/or terminate this Agreement. Such termination must be in writing to the Contractor upon thirty (30) days notice.

**Other Remedies:** If this Agreement is terminated in whole or in part by the HRSB as a result of the default of the Contractor, the HRSB shall be immediately entitled to withhold any and all further payments which may be due and owing to the Contractor, complete or hire a third party to complete the Services in a manner it determines to be expedient, or to do whatever else it deems prudent or expedient in the circumstances to complete the Services.

**Safety Default:** This Agreement may be immediately terminated by HRSB for non-compliance by Contractor of any of its obligations under Article 8 of this Agreement.

## DISPUTE RESOLUTION

**Disputes Generally:** Disputes between the Contractor and the HRSB as to the interpretation, application or administration of this Agreement or any failure to agree where agreement between the parties is called for, which are to be resolved between the parties, shall be settled by mediation and/or by arbitration.

**Use of Mediation.** Should HRSB choose to mediate a dispute:

Mediation shall take place on a confidential, without prejudice, basis with a single trained mediator who is a member of the Nova Scotia Arbitration and Mediation Society, jointly selected by the Contractor and the HRSB (the “**Mediator**”). The Mediator must be impartial and independent with no involvement in the dispute. This impartiality must be assessed by each of the parties prior to mediation. If a bias or perception of bias develops during the mediation, either party or the Mediator may terminate the mediation.

The Contractor, the HRSB and the Mediator shall agree on the fees, timing and any specific procedures and shall share the costs of mediation equally. All parties shall agree to and sign an agreement to mediate drawn up by the Mediator prior to mediation.

**10.3 Arbitration:** By written notice by one party to the other (a "Notice of Arbitration"), all disputes arising out of this Agreement, including its interpretation, must be submitted to binding arbitration in accordance with the provisions of the *Commercial Arbitration Act* (Nova Scotia), subject to the following:

- (a) The arbitration panel will consist of one arbitrator. If the parties fail to reach agreement on the selection of the arbitrator within 10 days following delivery of the Notice of Arbitration, any party may apply to The Supreme Court of Nova Scotia to appoint the arbitrator. The arbitrator will be qualified by education, training and industry experience to rule upon the particular dispute to be resolved.
- (b) The arbitrator will be instructed that time is of the essence in the arbitration proceeding and, in any event, the arbitration award must be made within 90 days of the submission of the dispute to arbitration and within 15 days of the conclusion of any hearing, or if there is no hearing, within 15 days of the delivery of written submissions.
- (c) The arbitration will take place in Halifax, Nova Scotia or such place as the parties may agree and will be conducted in the English language.
- (d) The arbitration award will be given in writing and will be final and binding on the parties. The award will give reasons and will deal with the question of costs of the arbitration and all related matters. The contractor and the HRSB shall share the costs of arbitration equally, unless otherwise determined by the Arbitrator.
- (e) The parties will keep all matters relating to the arbitration strictly confidential. The existence of the proceeding and any element of it (including any pleadings, briefs or other documents submitted or exchanged, any testimony or other oral submission in any award) will not be disclosed except to the arbitrator, the parties, their counsel and any person necessary to the conduct of the proceeding, except as may be required by law or as may be lawfully required in judicial proceedings relating to the arbitration.



## PERFORMANCE BOND

**Bond Requirement:** Contractor shall, on execution of this Agreement, provide and pay for a performance bond in the amount of fifty (50%) percent of the Contract Price and a labour and materials payment bond in the amount of fifty (50%) percent of the Contract Price issued by a bond company acceptable to the HRSB, to continue in force for one (1) year after substantial completion of the Services, covering the performance of all obligations of the Contractor and all warranties of the Contractor under this Agreement.  *Required*       *Not Required*

## WARRANTY

**Warranty:** The Contractor hereby warrants that:

it shall correct promptly, at Contractor's sole expense, defects or deficiencies in the Services as a result of workmanship or materials, which appear prior to the first (1<sup>st</sup>) anniversary of the date of completion of the Services, or such longer periods as may be specified for certain products or work in Appendix "C"; and

during the construction and warranty periods, defects or deficiencies in the Services, causing an emergency condition on the Lands or premises requiring immediate remedial/emergency repairs, outside of normal working hours, will be responded to by the HRSB's operations or maintenance staff. Costs for this emergency response will be the responsibility of the Contractor, and Contractor is hereby liable to indemnify HRSB for all such costs.

## CONFIDENTIALITY AND OWNERSHIP OF WORK PRODUCT

**Confidentiality:** Contractor shall:

not make use of any HRSB Confidential Information for its own personal gain or for any purpose other than is required to provide the Services;

not disclose any HRSB Confidential Information to any person except employees, consultants, subcontractors and agents who have a need to know such information consistent with the provision of the Services, but only after such person has properly assumed obligations identical in principle to those in this Section and Contractor ensures that such person at all times complies with those obligations

employ diligent efforts and exercise reasonable care to hold all HRSB Confidential Information in the strictest confidence;

not use HRSB's name for any marketing or promotional purposes and not make any public announcements or disclosure in respect of this Agreement or Contractor's relationship with HRSB without first obtaining written consent from HRSB; and

be liable to HRSB and indemnify HRSB for any breach of this Section by Contractor or its employees, consultants, subcontractors or agents.

**Terms of Agreements:** Neither party shall disclose the terms of this Agreement or amounts paid under it to any person without the other party's written consent, except to a party's employees, professional advisors and insurers who have a need to know such information, but only where the party ensures that such persons are under obligations of confidentiality identical in principle to those in this Section. HRSB shall not disclose Contractor's information respecting pricing or any information supplied by Contractor that is clearly marked "Confidential" to any person except HRSB's employees, consultants, subcontractors and agents who have a need to know such information.

**"HRSB Confidential Information"** refers to any and all information, material and data disclosed to Contractor by HRSB, or obtained by Contractor in connection with providing the Services, directly or indirectly, orally, in any written form, or in any magnetically or electronically recorded form, or by drawings or inspection of parts or equipment, and including but not limited to: (i) information, knowledge or data of an intellectual, technical, scientific, commercial or industrial nature, or of a financial, cost, pricing, or marketing nature relating to the business operations of HRSB; or (ii) any information supplied by HRSB that is clearly marked "Confidential"; but shall not include information in the public domain or information that at the time of disclosure was already known to Contractor on a non-confidential basis.

**Ownership of Work Product:** All property and intellectual property rights in all reports, designs, drawings, studies, specifications, software, materials, inventions and other work product created, produced or arising in connection with the performance of the Services, whether completed or in progress, and regardless of who was involved therewith, shall be owned exclusively by HRSB and either delivered to HRSB or made available for inspection by HRSB. HRSB's ownership of and title to the foregoing shall arise automatically upon its creation and not be subject to the payment of the Contract Price to Contractor. To the extent Contractor has any title to the foregoing, Contractor shall take and cause to be taken all necessary steps (including a waiver of any moral rights) to transfer title thereto to HRSB.

**Survival:** The provisions of this Article shall survive the expiration or termination of this Agreement.

## MISCELLANEOUS PROVISIONS

**Notices:** Communications in writing between the parties shall be considered to have been received by the addressee on the date of delivery if delivered by hand or by facsimile, or if sent by post, to have been delivered within FOUR (4) business days of the date of mailing, when addressed to the addresses in Appendix "C":

**Assignment:** This Agreement is not assignable by Contractor without the prior written consent of HRSB, which consent may be withheld arbitrarily. Any purported assignment by Contractor of any of its rights, duties, or obligations under this Agreement without HRSB's written consent, shall be voidable by HRSB at its option. Contractor shall not in any event be released from its duties and obligations under this Agreement. HRSB may assign this Agreement upon providing notice to without obtaining Contractor's consent.

**Binding Effect:** This Agreement shall be binding upon and enure to the benefit of each of HRSB and Contractor and their respective successors and permitted assigns.

**Interpretation:** In this Agreement, all references to 'dollars' or '\$' are to Canadian dollars unless stated otherwise. The insertion of headings is solely for convenience of reference and shall not affect the interpretation of any provision.

**Independent Contractor:** The parties agree that Contractor is an independent contractor, that nothing in this Agreement shall be construed as establishing or implying a relationship of master and servant between the parties, or any joint venture or partnership between the parties, and that nothing in this Agreement shall be deemed to constitute either of the parties as the agent of the other party or authorize either party to incur any expenses on behalf of the other party or to commit the other party in any way whatsoever. Contractor and its servants, agents or employees shall at no time be deemed to be servants, agents or employees of HRSB, or be deemed to be under the control or supervision of HRSB when carrying out the Services. Without the prior written consent of HRSB.

**No waiver:** No party shall be deemed to have waived the exercise of any right that it holds under this Agreement unless such waiver is made in writing. No waiver made with respect to any instance involving the exercise of any such right shall be deemed to be a waiver with respect to any other instance involving the exercise of that right or with respect to any other right.

**Governing Law:** This Agreement shall be governed by and interpreted in accordance with the laws of the Province of Nova Scotia and the laws of Canada applicable therein, excluding any conflict of laws rules that may apply therein. The parties hereby attorn to the non-exclusive jurisdiction of the courts of the Province of Nova Scotia, without prejudice to the rights of HRSB to take proceedings in any other jurisdiction. The parties hereby waive any right to a trial by jury.

**Time of the Essence:** Time shall be of the essence in this Agreement.

**Set-Off:** HRSB shall be entitled at all times to set off any amount owing from Contractor to HRSB against any amount due or owing to Contractor with respect to this Agreement.

**Entire Agreement; Invoice Terms of No Effect:** This Agreement constitutes the entire agreement of the parties concerning its subject matter and no other representation, warranties or agreements, either oral or written, shall be binding upon HRSB or Contractor. This Agreement supercedes and invalidates all prior agreements, understandings, negotiations, representations and warranties, whether oral or written, with respect thereto. The terms of this Agreement shall supersede any terms attached to Contractor's invoice, which terms shall not be applicable to this Agreement and shall not be considered to be Contractor's exceptions to the provisions of this Agreement.

**Counterparts:** The parties may execute this Agreement by facsimile or other electronic means and in separate counterparts each of which when so executed and delivered shall be an original, and all such counterparts taken together shall constitute one instrument.

## APPENDIX "B"

### RISK MANAGEMENT AND SAFETY

#### A. INDEMNIFICATION AND INSURANCE

##### 1. **Indemnity and Waiver:**

Contractor shall be liable to HRSB for and shall indemnify and save harmless HRSB from and against any and all claims, suits, demands, awards, actions, proceedings, losses, judgments, costs, damages, settlements or expenses (including legal costs on a solicitor and own client basis) suffered or incurred by HRSB that arise out of, result from, are based upon or are in any way connected with this Contract, including without limitation:

- (a) those resulting from any act or omission on the part of Contractor or its employees, agents and subcontractors;
- (b) those resulting from any action, suit or proceeding brought by any third party;
- (c) those brought in respect of personal injury (including injury resulting in death) or damage or destruction of tangible or intangible property, including HRSB's property;
- (d) those made under workers' compensation legislation;
- (e) those legal costs and fines resulting from the failure of Contractor, its employees, agents or subcontractors to comply with any applicable laws, regulations, by-laws, rules or orders of any government, authority or body having jurisdiction, whether identified in this Contract or applicable by-law;
- (f) those resulting from the release, discharge, seepage or other escape of any substance including chemicals, hazardous or toxic materials, substances, pollutants, contaminants or wastes, whether liquid, gaseous or of any other nature or for any breach of any applicable environmental legislation;
- (g) those resulting from any labourers', materialmen's, or mechanics' liens arising from or relating to the performance of the Contract;
- (h) those brought for actual, alleged, direct or contributory infringement of any patent, trademark, copyright, trade secret or other intellectual property right, including breach of obligations of confidentiality; and
- (i) any other claims, expenses, costs, and losses suffered, incurred or sustained by HRSB.

The foregoing liability, indemnification and hold harmless provisions shall apply to anything done or not done in connection with this Contract and by whomsoever made, regardless of whether it was caused by the negligence of Contractor or otherwise.

Contractor shall make no claim or demand against HRSB for any injury (including death), claim, expense, loss or damage to property suffered or sustained by Contractor or any other person which arises out of, or is connected, with this Contract or anything done or not done as required hereunder, or any other errors or omissions of Contractor, and hereby waives as against HRSB all such claims and demands.

The foregoing indemnity and waiver given by Contractor shall not apply to the extent of HRSB's own negligence. The onus of establishing that HRSB was negligent shall be upon Contractor. HRSB shall not be deemed to have caused or contributed thereto merely by reason of its knowledge, approval or acceptance of the materials, drawings,

specifications, supplies, equipment, procedures or services of Contractor.

For the purposes of this Section, any reference to "HRSB" shall include HRSB, together with the employees, directors, officers, superintendents, trustees, representatives and agents of HRSB; and any reference to "Contractor" shall include Contractor's directors, officers, employees, affiliates, representatives, agents and subcontractors.

## 2. Insurance:

Contractor shall, at its own expense, obtain and maintain during the term of this Contract, in a form and with an insurance company satisfactory to HRSB, policies of:

- (a) Commercial General Liability insurance with a limit of not less than Two Million Dollars (**\$5,000,000**) for any one loss or occurrence and in the aggregate with respect to bodily injury, personal injury and property damage, including loss of use thereof, which policy shall by its wording or by endorsement:
  - (i) include HRSB, its officers, directors, employees, agents and trustees as an additional insured with respect to the obligations assumed by Contractor under this Contract;
  - (ii) provide that, in relation to the interests of each additional insured, the Insurance shall not be invalidated by an action or inaction any other person other than the respective additional insured;
  - (iii) include a "cross liability" clause which shall have the effect of insuring each entity named in the policy as an insured in the same manner and to the same extent as if a separate policy had been issued to each;
  - (iv) extend to cover blanket Contractual liability, including the insurable liabilities assumed by Contractor under this Contract;
  - (v) extend to cover products and completed operations; such products and completed operations coverage, whether by specific policy endorsement respecting the services or by renewal of any annual practice policy, shall be kept in force during the supply of services and for a further period of 24 months following completion of supply of the services;
  - (vi) extend to cover non-owned auto liability coverage; and
  - (vii) not exclude any existing property of HRSB, but shall treat same as "third party property".
- (b) Employer's Liability Coverage which shall not be less than \$5,000,000 for each employee where Workers' Compensation coverage does not exist or the profession/trade has been indicated to be exempted from Workers' Compensation coverage.
- (c) Automobile public liability and property damage insurance in an amount not less than Two Million Dollars (\$2,000,000) all inclusive covering the ownership, use and operation of any motor vehicles and trailers which are owned, leased or controlled by the Contractor and used in connection with this Contract; and
- (d) Property "All Risks" insurance covering Contractor's owned property, including Contractor's equipment, where applicable, and property of others in the care, custody, or control of Contractor or for which the Contractor has assumed liability, all including while in transit or storage, on a replacement cost basis. With respect to any property of HRSB, such policy shall contain a loss payee

clause in favour of HRSB;  
(collectively, the "Insurance").

Contractor shall ensure that the above Insurance policies:

- (a) are endorsed to provide HRSB with not less than thirty (30) days written notice in advance of cancellation, change or amendments restricting coverage;
- (b) do not include a deductible that exceeds such maximum amount that a reasonably prudent business person would consider reasonable; and
- (c) take the form of an occurrence basis policy and not a claims-made policy.

Contractor shall, before any services are performed, provide HRSB with a copy of the certificates of insurance and, if requested by HRSB, the insurance policies evidencing all the coverage stipulated above, and HRSB may withhold payment of any invoice until it receives evidence of such coverage. Failure for any reason to furnish this proof at any time shall be a breach of the contract, allowing the HRSB to terminate the contract or at the HRSB's option, to supply such insurance and charge the cost to Contractor. The HRSB may require Contractor to have the HRSB added as an insured party to the insurance policy and/or require Contractor to furnish a certified copy of the policy for such insurance.

Contractor shall not make or cause to be made any modification, or alteration to the Insurance, nor do or leave anything undone, which may invalidate the Insurance coverage. Contractor shall be responsible for any deductible and excluded loss under the Insurance.

Contractor shall cause all subcontractors performing services to obtain and maintain the Insurance policies required by this Section.

Contractor agrees that the insurance coverage required to be maintained by it under the provisions of this Contract shall in no manner limit or restrict its liabilities under this Contract. HRSB reserves the right to maintain the insurance in good standing at Contractor's expense and to require Contractor to obtain additional insurance where, in HRSB's reasonable opinion, the circumstances so warrant.

## **B. COMPLIANCE WITH LEGISLATION AND REGULATIONS**

### **1. Compliance**

Contractor shall comply with and shall ensure all of its agents, employees and subcontractors comply with all applicable laws and regulations, including all safety, health and environmental requirements pursuant to any government permit, license, or authorization. Contractor shall at its cost obtain all permits and licenses required by any governing authority in order to enable Contractor to provide its goods and services and otherwise perform its obligations under the Contract.

### **2. Labour Code**

Contractor shall comply with all applicable provisions of the *Labour Code* (Nova Scotia) and the *Employment Standards Act* (Nova Scotia) and all regulations and amendments thereto.

### **3. Workers' Compensation Legislation**

Contractor shall comply with the *Worker's Compensation Act* (Nova Scotia) and regulations and amendments thereto, and:

- (a) if any employees perform or assist in the performance of this Contract, the Contractor shall submit, at any time requested by the HRSB, a letter from the Workers' Compensation Board (Nova Scotia) stating that Contractor has an account in good standing with the Worker's Compensation Board;
- (b) the Contractor will make the necessary returns to the Workers' Compensation Board in accordance with government regulations and will pay all fees and contributions required in connection therewith. The cost of compensation will be included in the price payable under the Contract; and
- (c) the Contractor shall submit a clearance from the Workers' Compensation Board that all fees and contributions have been paid before final payment is made by the HRSB under the Contract.

**4. Canada Safety Council and Associated Standards**

All electrical, electronic and gas-fired equipment must bear the required approval markings, being C.S.A. approved for entirely electrical or electronic equipment and C.G.A. or C.S.A. approved for gas fired equipment. All other similar equipment approvals must also be obtained. It shall be the responsibility of the Contractor to obtain all applicable approvals, at its own expense.

**5. Nova Scotia Occupational Health and Safety Legislation**

Contractor shall comply at all times with the Nova Scotia Occupational Health and Safety Act, Regulation and Code, and it's amendments thereto.

**C. SAFETY REQUIREMENTS**

**1. Safety Responsibility**

Contractor shall be solely responsible for ensuring the safety and health of its agents, employees and subcontractors and for ensuring that its activities do not compromise the safety of HRSB's operations. Contractor shall provide to its agents, employees and subcontractors, at its own expense, any and all safety gear required to protect against injuries during the performance of the services and shall ensure that its agents, employees and subcontractors are knowledgeable of and utilize safe practices in the provision of the services, such practices to be at least as stringent as those set out in HRSB's safety standards provided to Contractor from time to time.

**2. Project Site Protection and Safety**

The Contractor shall protect the HRSB's property, staff and students, the Contractor's staff and the public, from damage or injury by providing adequate precautions to make the work site a safe environment at all times. In addition to complying with any safety standards provided to the Contractor by HRSB, the Contractor shall:

- (a) provide all guards and fences and other safety equipment;
- (b) respond to reports of hazards by HRSB;
- (c) do the following when work generating vibration, noise or safety concerns (including without limitation jack hammering, shot blasting, sandblasting, concrete cutting and use of powder actuated fasteners) may affect HRSB property, staff, students or operations.
  - (i) coordinate with HRSB representatives;
  - (ii) schedule and coordinate hours of work with HRSB input; and

- (iii) stop operations generating vibration, noise or safety concerns when instructed by HRSB.
- (d) Contractor responsible to ensure all spaces directly beneath the roof work area are protected from potential damage of dust, debris or water infiltration or any other impact resulting from the roof replacement project. Such protection shall include installation of effective cover using minimum 4 mil plastic vapour barrier sheeting over all furniture, equipment, instruction aids, floors areas and any other items underneath the work space. Contractor must remove all sheeting upon completion of work and will be responsible for costs of restoration of damages caused by process of roof project or lack of adequate protection of property.

### 3. Hazardous Materials

The Contractor shall:

- (a) develop and implement a written "Hazardous Materials Information" document to ensure that all persons at the work site are made aware of the existence of any hazardous materials such as asbestos, lead-based products, and PCB's;

### D. CONTRACTOR EVALUATION

#### 1. Audit

The HRSB reserves the right to audit Contractors and their subcontractor's health and safety performances during the term of the Contract and upon its conclusion.

#### 2. Evaluation

The HRSB reserves the right to evaluate the performance of the Contractor and such evaluation will be based upon accident/injury data and adherence to this Schedule "C", the HRSB health and safety policies, applicable legislation, and periodic inspections and reports from HRSB employees. Information collected as part of such evaluations may be used for future reference.

### E. HRSB REMEDIES FOR CONTRACTOR NON-COMPLIANCE

#### 1. Emergency Work Stoppage

The HRSB has the authority to stop progress of the work whenever, in its opinion, such stoppage is desirable for any safety-related reason. The Contractor hereby agrees that no claim for loss of time or materials may be made with respect to such stoppage unless the claim for the time and materials and their value are certified in writing by the HRSB as allowable.

#### 2. Termination for Non-Compliance

HRSB may terminate this Contract for non-compliance with health, safety, environmental and other applicable legislation and good industry practice on the part of the Contractor or any subcontractor of the Contractor, as constituting a material breach of this Contract. In addition, the HRSB reserves the right to stop the work of the Contractor in the event of Contractor's non-compliance with applicable legislation or good industry practice. Such work stoppages shall not postpone any agreed to completion dates and any additional cost



resulting from such work stoppages shall be borne by the Contractor. Work shall not resume until the Contractor rectifies the reason for non-compliance, to HRSB's satisfaction.

**3. Non-Exclusive Remedies**

Contractor acknowledges and agrees that the foregoing remedies available to HRSB are non-exclusive to, and may be exercised in conjunction with, any other rights or remedies available to HRSB, under the Contract, at law or in equity, in the event of threatened or actual breach of this Contract, including injunctive relief.

SAMPLE ONLY

**APPENDIX "C"**

**DESCRIPTION OF SERVICES**

- Description of Services to be performed by Contractor**, including any applicable standards of performance:

**Description of Work:**

**As per Tender #      drawings, specifications and scope of work**

- Municipal and Legal Description of the Lands:**

**Location of Work**

- Term:** completion of work by ,

- Invoicing:** Services are to be paid for by HRSB:

- By scheduled progress payments (as agreed by both parties)
- By single invoice upon project completion

- Holdbacks:** In compliance with "Section 13 – Holdbacks" of the *Builder's Lien Act of Nova Scotia (incl. amendments)*, a holdback in the amount of ten percent (10%) of the contract may be held up to ninety (90) days after completion of the work, to the satisfaction of the Board.

- HRSB Project Manager /Contractor Contact Information:**

<b>CONTRACTOR INFORMATION</b>	<b>HRSB INFORMATION</b>
Name: Jurisdiction of incorporation:  Address: Attention: Telephone: Facsimile: E-mail: GST Registration #: WCB Registration #:	HRSB Representatives: Name:  Department: <b>Operations Services</b> Address: <b>33 Spectacle Lake Drive</b> <b>Dartmouth, N.S., B3B 1X7</b> Telephone: <b>902 464-2000 Ext.</b> Facsimile: <b>902-</b> E-mail:

\_\_\_\_\_                      \_\_\_\_\_  
 Contractor's Initials              HRSB's Initials

**Exhibit A**

**Invitation To Tender**

**PROJECT SPECIFICATIONS/DRAWINGS WERE INCLUDED IN TENDER DOCUMENT AND ARE CONSIDERED PART OF THIS CONTRACT EVEN THOUGH THEY ARE NOT ATTACHED TO THIS DOCUMENT**

**Exhibit B**

**Response to Invitation to Tender**

**A COPY OF THE SUCCESSFUL CONTRACTOR'S BID SUBMISSION IS ON FILE IN  
THE PURCHASING DEPARTMENT - TENDER #3437**

**APPENDIX "D"**

**UNDERTAKING TO COMPLY FORM  
AND CONTRACTOR SAFETY CHECKLIST**

**UNDERTAKING TO COMPLY**

**Name of Contractor:**

**(the "Contractor")**

**Description of Agreement:**

**Site Location:**

**(the "Agreement")**

7. The Contractor hereby undertakes to HRSB:  
to comply with all health, safety and environmental legislation in the performance of this Agreement; and  
to maintain a safe and healthy work environment during the performance of this Agreement.
8. The Contractor hereby agrees with HRSB:  
that compliance with all health, safety and environmental legislation is a condition of this Agreement and that non-compliance with the same may, in HRSB's discretion, lead to the termination of this Agreement; and  
to permit HRSB to audit the Contractor's health, safety and environmental records during the term of this Agreement and upon its conclusion and to cooperate fully with any such audit(s).
9. The Contractor understands that, at HRSB's discretion, any Contractor safety deficiencies will be addressed by HRSB in the following progressive steps:  
the problems will be identified to the Contractor (site supervisor);  
the Contractor's head office will be contacted about the problem, orally and later in writing;  
if required by law to report the problem to a Provincial and or Federal Ministry, HRSB will immediately do so;  
if not required by law to report the problem, and the problem remains unresolved, HRSB may report the problem; and  
the Agreement may, in HRSB's discretion, be suspended or terminated and/or payment withheld by HRSB.

- 10. The Contractor acknowledges and agrees with HRSB that, depending upon the nature and/or seriousness of the deficiency, HRSB reserves the right to bypass any or all of the steps described in Section 3.
- 11. **Prime Contractor Designation:** The Contractor and the HRSB hereby agree that the Contractor shall, pursuant to Section 8.4 of the Agreement shall be the Prime Contractor.

The undersigned hereby confirms that he/she has the authority to bind the Contractor:

**CONTRACTOR**

**HALIFAX REGIONAL  
SCHOOL BOARD**

\_\_\_\_\_  
*FULL COMPANY NAME*

\_\_\_\_\_  
*PRINT NAME*

\_\_\_\_\_  
*AUTHORIZED SIGNATURE*

\_\_\_\_\_  
*POSITION*

\_\_\_\_\_  
*DATE*

\_\_\_\_\_  
*PRINT NAME*

\_\_\_\_\_  
*AUTHORIZED SIGNATURE*

\_\_\_\_\_  
*POSITION*

\_\_\_\_\_  
*DATE*

SAMPLE ONLY

**PRE-CONSTRUCTION MEETING**  
**CONTRACTOR SAFETY CHECKLIST PAGE 1**

<b>MEETING DATE:</b>	<b>TENDER #:</b>
----------------------	------------------

**SITE LOCATION:**

**COMPANY NAME:**

**CONTRACTOR REPRESENTATIVE::**

**HRSB REPRESENTATIVE::**

<b>√ Means complied to</b>	<b>X Means not complied with</b>	<b>n/a means not applicable</b>
----------------------------	----------------------------------	---------------------------------

- |   |  |
|---|--|
| <p>1. Notice of Project filed with Nova Scotia Infrastructure (if applicable) <input type="checkbox"/></p> <p>2. Review Board Safety Compliance Undertaking to Comply Form Signed <input type="checkbox"/></p> <p>Progressive Disciplinary Action Reviewed <input type="checkbox"/></p> <p>3. Contractor Health and Safety Policy <input type="checkbox"/></p> <p>Prime Contractor and Safety Management Certificate <input type="checkbox"/></p> <p>4. Health &amp; Safety Representatives/Joint Site Health &amp; Safety Committee <input type="checkbox"/></p> <p>Name and Phone _____ <input type="checkbox"/></p> <p>5. Personal Protective Equipment:</p> <p>Hard Hats <input type="checkbox"/></p> <p>Footwear <input type="checkbox"/></p> <p>Safety Glasses <input type="checkbox"/></p> | <p>8. Contractor Staff Training: Emergency Response <input type="checkbox"/></p> <p>WHMIS Training Verification <input type="checkbox"/></p> <p>O H &amp; S <input type="checkbox"/></p> <p>MSDS Received <input type="checkbox"/></p> <p>Scaffold <input type="checkbox"/></p> <p>Confined Space Code of Practice <input type="checkbox"/></p> <p>TDG Training Verification <input type="checkbox"/></p> <p>Working Alone <input type="checkbox"/></p> <p>9. Review Contractor Signage &amp; Barricades <input type="checkbox"/></p> <p>10. Written Work Site Hazard Assessment and Control Plan/Schedule Submitted <input type="checkbox"/></p> <p>11. Building Fire Plan <input type="checkbox"/></p> |
|---|--|

SAMPLE ONLY

**CONTRACTOR SAFETY CHECKLIST – PAGE 2**

- |   |                          |   |                          |
|---|--------------------------|---|--------------------------|
| Hearing   | <input type="checkbox"/> | 12. Accident Investigation/Notification/Reporting Procedure | <input type="checkbox"/> |
| Dust & Fumes  | <input type="checkbox"/> |   |                          |
| Face Protection   | <input type="checkbox"/> |   |                          |
| Others: _____   | <input type="checkbox"/> | 13. Contingency Plan for Control & Clean up of a Spill      | <input type="checkbox"/> |
| _____   | <input type="checkbox"/> |   |                          |
| _____   | <input type="checkbox"/> | 14. Fire Protection/Extinguishers                           | <input type="checkbox"/> |
|   |                          |   |                          |
| 6. Equipment Certification  |                          | 15. First Aid Kits on Site                                  | <input type="checkbox"/> |
| Trench Boxes  | <input type="checkbox"/> |   |                          |
|   |                          | 16. First Aiders on Staff                                   | <input type="checkbox"/> |
| Boom Cranes   | <input type="checkbox"/> | Names: _____  |                          |
| Scaffolds   | <input type="checkbox"/> |   |                          |
| Others: _____   | <input type="checkbox"/> | 17. Fall Protection /Safety Harness                         | <input type="checkbox"/> |
| _____   | <input type="checkbox"/> |   |                          |
| _____   | <input type="checkbox"/> | 18. Methane gas Detection in Sewer                          | <input type="checkbox"/> |
|   |                          |   |                          |
| 7. Provision of Hazardous Material Information to Contract                      | <input type="checkbox"/> | 19. Clean Up - Good Housekeeping                            | <input type="checkbox"/> |
| Confirmation of Employee Awareness of Hazardous Material                        | <input type="checkbox"/> |   |                          |
| Asbestos  | <input type="checkbox"/> | 20. Weekly Safety Talks/Meetings                            | <input type="checkbox"/> |
| Lead  | <input type="checkbox"/> |   |                          |
| PCB   |                          |   |                          |
| Confirmation that Prime Contractor reviewed Asbestos Inventory at the work site | <input type="checkbox"/> | 21. Other Issues  | <input type="checkbox"/> |

SAMPLE ONLY







## APPENDIX E

### **Project Safety Plan Outline**

During the planning of each project, environmental and occupational health and safety issues will be assessed like any other key project component.

Prior to beginning a new project, tendering Contractors shall examine the work area to identify potentially hazardous site specific situations.

Once identified, these hazards should be prioritized on this Hazard Assessments/Project Safety Plan Outline and corrective *actions* noted to eliminate or control each hazard. The dates of when and names of the persons who are responsible for completing the *action* should also be assigned.

Copies of the completed Safety Plan Outline shall be submitted as part of the tender document submittal, sent to the HRSB Operations Services Regional Manager, made available on the job site and communicated to the workers.

---

---

Project Name: \_\_\_\_\_

Project Location: \_\_\_\_\_

Project Start date: \_\_\_\_\_

Project End date: \_\_\_\_\_

Company Name: \_\_\_\_\_

Completed by: \_\_\_\_\_  
(Contractor's project manager)

Date: \_\_\_\_\_

Copy to: \_\_\_\_\_

**PLANNING:**

Does the Contractor's Occupational Health and Safety Program deal with the work activities associated with this project?    Yes                       No

Describe tasks to be undertaken: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**HAZARDS ASSESSMENT:**

Identify the hazards that could present themselves on this project (e.g. live electrical wires, over water, confined space, etc) and describe what steps will be taken to prevent an incident (e.g. cover up, de-energize, safe work practices, netting, etc). Prioritize from #1 as needing immediate action.

#	Hazard	Required Action	Completed by	Date
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				

**ENVIRONMENTAL ASSESSMENT:**

Identify the environmental issues that could present themselves on this project (e.g. oil spills, asbestos, etc.) and describe the action that will be taken to eliminate or reduce the risk of occurrence (e.g. mop kits, air sampling, etc.)

#	Hazard	Required Action	Completed by	Date
1				
2				
3				
4				
5				

**EMERGENCY RESPONSE:**

In the event of an incident, pre-plan the response and write up the procedures. Minimally, the following list should be completed and posted on site:

Contact	Phone #	Contact	Phone #
Fire	911	Poison Control	428-8161
Ambulance	911	Dangerous Goods	1-800-565-1633
Doctor	911	Waste Disposal	
Police	911	Insurance	
HRSB Office	493-5110	Min/Dept of Labour	1-800-952-2687
Min./Dept.of Transport.		Min/Dept of Environment	1-800-565-1633

- Identify and arrange source of first aid, ambulance and rescue.
- Accidents will be reported to: \_\_\_\_\_
- Accidents will be investigated by: \_\_\_\_\_
- Back-up call to: \_\_\_\_\_
- HRSB # emergency/after hours: day 493-5110 after 4:00 pm 442-2476

**SAFETY MEETINGS:**

On this project, given the nature of the work and the anticipated size of the work force, the following frequency will apply:

Site meetings \_\_\_\_\_

Site Audits \_\_\_\_\_

Follow up with HRSB Manager: \_\_\_\_\_

**SITE IMPLEMENTATION:**

- Health and Safety Rep & Safety Committee:  
Establish liaison between HRSB, Contractor, site administration  
First Aid, PPE, other safety items as required.
  
- Documentation:  
Applicable MSDS  
Safety program  
Applicable work procedures  
Permits  
First Aid Certification

**TRAINING:**

The following training/testing will be mandatory on site:

1) \_\_\_\_\_

\_\_\_\_\_

2) \_\_\_\_\_

\_\_\_\_\_

3) \_\_\_\_\_

\_\_\_\_\_

**TENTATIVE SCHEDULE OF WORK:**

- 1) Date Project Will Commence: \_\_\_\_\_
- 2) Number of Weeks to Complete Project: \_\_\_\_\_ weeks
- 3) Expected Completion Date: \_\_\_\_\_

***NOTE:***

***Within five (5) business days the successful bidder shall provide a schedule clearly indicating timelines for completion of all aspects of the project.***

## **APPENDIX F**

### ***CONTRACTOR'S CHECKLIST***

Enclose the following documents with your bid:

- Bid Security as required in Clause 1.3 (e)*** in the amount of 10% of the Contract Price (before HST).
- Contract Security for bids over \$100,000 as required in Clause 1.3 (f).***
- Certificate of Insurance*** indicating a minimum of **\$5,000,000 Commercial General Liability Insurance** per occurrence and **Commercial Auto Liability Insurance** covering all owned, non-owned and hired vehicles for a minimum combined single limit of **\$2,000,000** per occurrence and **Builder's Risk Insurance** in the amount of the contract price.
- Tentative Work Schedule (Timelines)*** – Subsequently, within five (5) business days of tender award the successful bidder shall provide a schedule clearly indicating timelines for completion of all aspects of the project.
- Workers' Compensation Board Letter*** of Good Standing
- Certificate of Recognition from one of the seven safety audit companies that jointly sign with the WCB:***
  - East Coast Mobile Medical Inc.
  - HSE Integrated
  - Nova Scotia Construction Safety Association
  - Nova Scotia Trucking Safety Association
  - Occupational Health & Educational Services (2002) Inc.
  - Safety Services Nova Scotia
  - Stantec Inc.

This list can be found on WCB's website: [www.wcb.ns.ca](http://www.wcb.ns.ca).
- Completed HRSB Safety Plan***
- Applicable Warranty Information***

**THIS SPECIFICATION COVERS THE INSTALLATION OF TWO PLY MODIFIED ROOFING SYSTEMS ON METAL DECKS AND WOOD DECKS WITHOUT THE USE OF HOT ASPHALT.**

**SYSTEMS FROM TWO MANUFACTURES ARE SPECIFIED AS FOLLOWS:**

**1. FAST-N-WELD BY IKO ON WOOD DECKS.**

- wood deck
- double layer of 1/4" recovery board secured with screws and plates.
- torched 180 base sheet as a vapour barrier
- Type 2 insulation adhered with IKO Millennium two part low rise adhesive
- insulation cover board with factory applied base sheet adhered with IKO Millennium two part low rise adhesive
- cap sheet torched.

**2. FAST-N-WELD BY IKO ON METAL DECKS.**

- metal deck
- primed roof board
- torched 180 base sheet as a vapour barrier
- Type 1 insulation
- insulation cover board with factory applied base sheet secured with screws and plates and all screws covered with base sheet patches.
- cap sheet torched

**3. SOPRAFIX BY SOPREMA ON WOOD DECKS**

- wood deck
- double layer of 1/4" recovery board secured with screws and plates.
- torched 180 base sheet as a vapour barrier
- Type 2 insulation adhered with Soprema Duotack two part low rise adhesive
- insulation cover board with factory applied base sheet adhered with Soprema Duotack two part low rise adhesive
- cap sheet torched.

**4. SOPRAFIX BY SOPREMA ON METAL DECKS**

- metal deck
- primed roof board
- torched 180 base sheet as a vapour barrier
- Type 1 insulation
- insulation cover board with factory applied base sheet secured with screws and plates and all screws covered with base sheet patches.
- cap sheet torched

**PART 1 - GENERAL**

**1.1 RELATED WORK  
PERFORMED BY  
OWNER**

- .1 The owner's mechanical contractor, Black & MacDonald, will disconnect power to fans. The roofer is to lift fans and raise curbs to



JUNE 2014

12" above new roof membrane level. Black & MacDonald will extend duct work as required and re-install the fans.

- .2 The owner's mechanical contractor, Black & MacDonald will disconnect air conditioning units on Grosvenor Wentworth to allow the roofer to raise the existing prefabricated metal curbs to 12" above the drainage plane of the roof and cover the curbs with membrane. Black & MacDonald will then reset the units and reconnect them.
- .3 All roof drains are to be re-used unless otherwise noted on the drawings. The owner's mechanical contractor, Black & MacDonald will temporarily lower all drains as stripping off proceeds and re install existing drains in the new roof.
- .4 Refer to the plan for each roof for information on drains which are to be replaced. Replacement drains are to be supplied by the roofer and installed by Black & MacDonald.
- .5 The owner will provide Black & MacDonald with names of all who attend the pretender meeting. Black & MacDonald will provide all bidders with their price for the services in items 1, 2, 3 and 4 above. The roofer is to include the price quoted by Black & MacDonald in their tender price.

#### 1.2 RELATED WORK PERFORMED BY THE ROOFER

- .1 Prepare existing roof drains which are to be re-used by drilling out broken studs and re-tapping.

#### 1.3 REFERENCES

- .1 CSA B35.3-1962 Tapping and Drive Screws (Slotted and Recessed Head, Thread).
- .2 CGSB 37-GP-56M-80 Membrane, Modified, Bituminous, Prefabricated, and Reinforced for Roofing.
- .3 Canadian Roofing Contractors Association - CRCA Roofing Specifications Manual - latest edition.
- .4 CAN/ULC-S701-01, Thermal Insulation, Polystyrene Boards and Pipe Covering.
- .5 CAN/ULC-S706-02, Standard for Wood Fibre Thermal Insulation for Buildings.

#### 1.4 SHOP DRAWINGS

- .1 Provide tapered insulation shop drawing.
- .2 Provide product data for each component / material to be provided.

#### 1.5 STORAGE AND HANDLING

- .1 Provide and maintain dry, off-ground weatherproof storage.
- .2 Store rolls of membrane in upright position.

JUNE 2014

- .3 Remove only in quantities required for same day use.
- .4 Place plywood runways over work to enable movement of material and other traffic.
- .5 Store caulking at +5°C minimum.
- .6 Store insulation protected from weather and deleterious materials.

#### 1.6 PROTECTION

- .1 Fire Extinguishers: maintain one stored pressure rechargeable type with hose and shut off nozzle, ULC labeled for A,B, and C class protection. One size 9 kg unit on the roof per torch applicator, within 6 m of the applicator.
- .2 Maintain fire watch for 3 hours after each day's roofing operations cease. See HRSB front end document.
- .3 Cover all interior spaces with 6 mil polyethylene to protect the building contents from dust related to the re-roofing process overhead. See HRSB front end document.
- .4 Keep the dumpster a minimum of 35 feet away from the building during all non working hours. See HRSB front end document.

#### 1.7 ENVIRONMENTAL REQUIREMENTS

- .1 Do not install roofing when wind chill temperature remains below -18 degrees C for torch application.
- .2 Install roofing on dry deck, free of snow and ice, use only dry materials and apply only during weather that will not introduce moisture into roofing system.

#### 1.8 WARRANTY

- .1 Contractor hereby warrants that modified bituminous roofing and membrane flashings as follows:
  - .1 2 year CRCA materials and workmanship against leaks and blow off.
  - .2 10 year material warranty that the membrane will perform as a roofing material.
- .2 1 year CRCA warranty against defects of materials and workmanship for the sheet metal work.

#### 1.9 COMPATIBILITY

- .1 Compatibility between components of roofing system is essential. Provide written declaration to Architect stating that materials and components, as assembled in system, meet this requirement.

## PART 2 - PRODUCTS

### 2.1 DECK COVER BOARD - WOOD DECK

- .1 Recovery board - size 4' x 5' - film / film
  - .1 Acceptable material
    - .1 IKO Protectoboard 6 mm thick
    - .2 Sopraboard 6 mm thick.

### 2.2 DECK COVER BOARD - STEEL DECK

- .1 Fibreglass mat faced gypsum roof board, coated:
  - .1 Thickness: 13mm.
  - .2 Width: 1220mm.
  - .3 Length: 1220 and 2440mm.
  - .4 Weight: 9.64 kg/m2 (1.98 lb/sq. ft.) nominal.
  - .5 Surfacing: Fibreglass mat, with non-asphaltic, highly filled coating on one side.
  - .6 Flexural Strength, parallel (ASTM C 473): 80 lbs., minimum.
  - .7 Flute Spanability (ASTM E 661): 5 inches.
  - .8 Permeance (ASTM E 96): 35 perms, maximum.
  - .9 R-Value (ASTM C 518): 0.56 minimum.
  - .10 Water Absorption (ASTM C 1177): 10 percent of weight, maximum.
  - .11 Acceptable material:
    - .1 DensDeck Prime Roof Board by Georgia Pacific.
    - .2 GlasRoc Roof Board by CertainTeed.

### 2.3 VAPOUR BARRIER

- .1 Vapour Barrier : to CGSB 37-GP-56M, Styrene-Butadiene-Styrene (SBS) elastomeric polymer, prefabricated sheet, polyester reinforcement, weighing 180 g/m2 .
  - .1 Type 2, fully adhered.
  - .2 Class C-plain surfaced.
  - .3 Grade 2 heavy duty service.
  - .4 Top and bottom surfaces:
    - .1 Polyethylene / sanded
  - .5 Acceptable material:
    - .1 Modiflex MP - 180 FS Base by IKO
    - .2 Sopralene 180 SP by Soprema

### 2.4 EXPANDED POLYSTYRENE INSULATION

- .1 Polystyrene: to ULC-CAN-S701,
  - .2 Type 1 for use in mechanically secured installations and Type 2 for installations using two part low rise foam adhesive.
  - .3 Size 4' x 4' square edge.
  - .4 Acceptable material: Trueroof by Truefoam.



JUNE 2014

- .5 Insulation to be provided in single thickness pieces unless otherwise noted on the drawings.
  - .6 Configuration of tapered insulation as shown on the drawings.
  - .7 Sump insulation by 1" at drains.
- 2.5 TWO PART LOW RISE FOAM ADHESIVE
- .1 Two part low rise polyurethane adhesive for roofing insulation and overlay boards.  
Acceptable material:
    - .1 IKO Millennium
    - .2 Soprema Duotack
- 2.6 INSULATION COVER BOARD WITH FACTORY APPLIED BASE SHEET
- .1 High strength wood fiberboard impregnated with a fire retardant with a factory laminated base sheet membrane. The top face of the membrane is covered with a thermofusible plastic film.  
Acceptable material:
    - .1 Soprabase FR 180 from Soprema
    - .2 Lexbase FR 180 from IKO
- 2.7 CAP SHEET MEMBRANE
- .1 Cap sheet: to CGSB 37-GP-56M, Styrene-Butadiene-Styrene (SBS) elastomeric polymer prefabricated sheet, polyester reinforcement, weighing 250 g/m2 .
    - .1 Type 1, fully adhered.
    - .2 Class A-granule surfaced.
    - .3 Grade 2 heavy duty service.
    - .4 Bottom surface polyethylene
    - .5 Acceptable material:
      - .1 PrevENT TP 250 Cap by IKO
      - .2 Sopralene Flam 250 FR Granules by Soprema
- 2.8 SEALERS
- .1 Modified plastic cement: asphalt, to CAN/CGSB-37.5.
  - .2 Sealing compound: to CAN/CGSB037.29, rubber asphalt type.
- 2.9 METAL FLASHING
- .1 22 gauge pre-painted steel - Colorite HMP finish.
  - .2 Color - to be chosen from the manufacturers standard range.
- 2.10 FASTENERS
- .1 #12 FM approved screws and plates as approved by the membrane manufacturer.
  - .2 Color Mate Screws to match metal color.

JUNE 2014

- .3 Zamac pin bolts - 1/4" diameter - length as required.
  - .4 Termination bars 1/8" x 1" punched at 6" c/c
- 2.11 ROOF DRAINS
- .1 Reuse roof drains where noted on drawings. Drill out and re-tap for all broken studs.
  - .2 On Roof D at Grosvenor Wentworth use Zurn 181-C-R 4" NH with Plain Bronze Dome and sump receiver with under deck clamps. Replace downspouts with new heavy walled plastic pipe complete with wall straps made from 1/8" x 2" aluminum flat bar.
  - .3 Where noted on drawings replace internal roof drains with new Zurn Z-100 drains with under deck clamps and metal domes except for
- 2.12 PLYWOOD AND WOOD
- .1 Wood for blocking to be No. 1 or better S-P-F **NOT PRESSURE TREATED.**
  - .2 Plywood to be softwood plywood - select.
- 2.13 PLUMBING VENT FLASHING
- .1 Thaler Stackjack Flashing SJ-43.
- 2.14 EXPANSION AND DEFLECTION JOINTS
- .1 Supply and install Redline 100 as a deflection joint on Hillside Park and Redline 20 as an expansion joint on J. L. Ilsley
- 2.15 ROOF ACCESS AT HILLSIDE PARK
- .1 At Hillside Park supply and install new new Bilco S-50 roof hatches with Bilco LU-1 posts and access ladders at two locations as detailed on the drawings.
  - .2 At Hillside Park supply and install one aluminum ladder and landing platform system for access to the gym roof as detailed on the drawings.
- PART 3 - EXECUTION**
- 3.1 WORKMANSHIP
- .1 Do roofing work in accordance with applicable, standard in Canadian Roofing Contractors Association (CRCA) Roofing Specifications Manual, latest edition, and the printed instructions from the membrane manufacturer.
- 3.2 REMOVALS
- .1 Remove the existing roof system to the level of the existing wood or metal deck. Dispose of all debris legally off site.
  - .2 Clean all debris out of deck flutes.

- .3 Remove all gravity vents and gooseneck vents and save for re-installation.

### 3.3 PROTECTION

- .1 Cover walls and adjacent work where materials are hoisted or used.
- .2 Cover interior spaces with 6 mil polyethylene to keep construction dust off the building contents. See the front end of the HRSB tender document.
- .3 Keep dumpster a minimum of 35 feet away from the building as per directions in the HRSB tender document front end.
- .4 Use warning signs and barriers. Maintain in good order until completion of work.
- .5 Clean off drips and smears of bituminous material immediately.
- .6 Ensure that all roof drains remain operation from the start of the project until completion. Clamping rings are to be re-installed at the end of every day.  
  
Temporary drains must be secured with MJ coupling so a blocked drain line can not back up and drain into the building. Use unequal diameter MJ couplings where required to make these connections.
- .7 Protect roof from traffic and damage. Comply with precautions deemed necessary by Architect.
- .8 Do an under deck inspection before starting work to verify where conduits and cables are attached direct to the deck and avoid these areas.
- .9 At end of each day's work or when stoppage occurs due to inclement weather, provide protection for completed work and materials out of storage.

### 3.4 EXAMINATION ROOF DECKS

- .1 Strip existing roof off to bare wood or metal deck and dispose of all material legally off site.
- .2 Examine roof decks and immediately inform the Architect in writing of any defects.
- .3 Prior to commencement of work ensure:
  - .1 All roof edge blocking has been installed and is secure.
  - .2 Roof drains have been prepared..
  - .3 Fan, goose neck and gravity vent curbs have been raised to 12" above new roof level.



JUNE 2014

3.5 INSTALLATION OF  
DECK COVER BOARD -  
WOOD DECK

- .1 Secure a double layer of 1/4" recovery board to the wood deck with #12 x 2 1/4" FM approved screws and plates. Fastener density to be one per 2 sq. ft. in field, one per 1.5 sq. ft. in perimeter width and one per sq. ft. in corners. Spacing from edges and corners of sheet to be as per manufactures written directions.
- .2 Edge width to be six feet.

3.6 INSTALLATION OF  
DECK COVER BOARD -  
METAL DECK

- .1 Secure 5/8" deck cover board with 8 screws and plates per 4' x 8' sheet. Prime cover board with approved primer.
- .2 At Elizabeth Sutherland the deck cover board is to be secured at 8 fasteners per 4' x 8' sheet in the field, 12 in the edge width and 16 in the corner because this roofing system is adhered to that surface with two part adhesive.

3.7 INSTALLATION OF  
VAPOUR BARRIER ON  
DECK COVER BOARD  
AND RECOVERY BOARD

- .1 All roofs have some areas of plywood on the plane of the roof deck as well as stacked wood blocking which has to be covered with base sheet to act as the vapour barrier as well as a temporary roof.  
  
To ensure that membrane is not torched direct to wood a base sheet is to be installed dry in these areas and covered with one layer of 1/4" recovery board and those boards secured with screws and plates and then the base sheet torched to the surface of the recovery board.
- .2 Torch specified base sheet solid to the recovery board with edge and end laps as specified by the manufacturer.

3.8 INSTALLATION OF  
INSULATION ON  
WOOD DECKS

- .1 Install insulation with 1" diameter beads of specified two part low rise adhesive.
- .2 Density of beads to be 12" c/c in the field, 9" c/c in the edge width and 6" c/c in the corner.
- .3 Weight down each block of insulation with four 5 gallon buckets of ballast until the adhesive has achieved a full set.
- .4 Edge width to be as specified in 3.5 above

3.9 INSTALLATION OF  
INSULATION ON  
METAL DECKS

- .1 Install insulation over vapour barrier in single layers.
- .2 Cut end pieces to fit tightly.

- .3 Mechanically secure the insulation with sufficient fasteners to keep all joints tight until the insulation cover board is installed.

### 3.10 INSTALLATION OF INSULATION COVER BOARD / BASE SHEET ON WOOD DECKS

- .1 Install insulation with 1" diameter beads of specified two part low rise adhesive.
- .2 Density of beads to be 12" c/c in the field, 9" c/c in the edge width and 6" c/c in the corner.
- .3 Walk boards into full contact.
- .4 Edge width to be as specified in 3.5 above.

### 3.11 INSTALLATION OF INSULATION COVER BOARD / BASE SHEET ON METAL DECKS

- .1 Secure the insulation cover board with factory installed base sheet to the fastening patterns recommended by the manufacture for FM 1-90 wind uplift rating including increased density for perimeter and corner.

### 3.12 EXPOSED MEMBRANE APPLICATION

- .1 Cap sheet application:
  - .1 Starting at low point on roof, perpendicular to slope, unroll cap sheet, align and re-roll from both ends.
  - .2 Unroll and torch cap sheet onto base sheet taking care not to burn membrane or its reinforcement.
  - .3 Lap sheets 75 mm minimum for side laps and 150 mm minimum for end laps. Offset joints in cap sheet 300 mm minimum from those in base sheet.
  - .4 Application to be free of blisters, fishmouths and wrinkles.
  - .5 Do membrane application in accordance with manufacturer's recommendations.
- .2 Base sheet flashing application:
  - .1 Complete installation of flashing base sheet stripping prior to installing membrane cap sheet.
  - .2 Torch base and cap sheet onto substrate in 1 meter wide strips.
  - .3 Lap flashing base sheet to membrane base sheet minimum 150 mm and seal by torch welding.
  - .4 Lap flashing cap sheet to membrane cap sheet 250 mm minimum and torch weld.
  - .5 Provide 75 mm minimum side lap and seal.
  - .6 Properly secure flashings to their support, without sags, blisters, fish mouths or wrinkles.
  - .7 Do work in accordance with manufacturer's recommendations.



JUNE 2014

- .3 Self adhesive membrane flashing application:
  - .1 Prime the exterior wood surface of the roof edge blocking and install self adhesive membrane over the full surface. Lap modified bituminous flashing membrane down over the self adhesive membrane without torching and nail with roofing nails at 6" c/c along the edge of the membrane.

3.13 CAPPING EXPOSED  
SCREWS IN GYMS

- .1 In gymnasiums screw points must be capped if the screw extends below the bottom of the metal deck.
- .2 Gymnasiums roofs exist at Prospect Road and J. L Ilsley.  
  
Prospect Road has sloped metal deck and the insulation will be uniform thickness. The insulation thickness has been chosen to allow use of a standard screw length that will not extend below the bottom of the roof deck.  
  
On J.L. Ilsley the roof insulation is tapered. If screws extend below the bottom of the deck they are to be cut to 1" and capped with electrical Marrettes.

3.14 METAL FLASHING

- .1 Install as detailed using CRCA approved metal fabrication methods.

3.15 CLEANING

- .1 Remove bituminous markings from finished surfaces.
- .2 In areas where finished surfaces are soiled by work of this section. Consult manufacturer of surfaces for cleaning advice and comply with their documented instructions.
- .3 Repair or replace defaced or disfigured finishes caused by work of this section.

3.16 FIELD QUALITY  
CONTROL

- .1 Periodic site review of roofing application will be carried out by Architect.

**END OF SECTION**

## PART 1 - GENERAL

- 1.1 SECTION INCLUDES .1 Requirements for the installation of preformed metal cladding/siding.
- 1.2 RELATED SECTIONS .1 Section 07 55 00 - Modified Bituminous Membrane Roofing.
- 1.3 REFERENCES .1 American National Standards Institute (ANSI).  
.1 ANSI B18.6.4-99, Thread Forming and Thread Cutting Tapping Screws and Metallic Drive Screws.  
.2 Canadian General Standards Board (CGSB).  
.1 CAN/CGSB-51.32-M77, Sheathing, Membrane, Breather Type.  
.2 CAN/CGSB-93.3-M91, Prefinished Galvanized and Aluminum-Zinc Alloy Steel Sheet for Residential Use.  
.3 CAN/CGSB-93.4-92, Galvanized and Aluminum-Zinc Alloy Coated Steel Siding Soffits and Fascia, Prefinished, Residential.  
.3 Canadian Standards Association (CSA International).  
.1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
- 1.4 SUBMITTALS .1 Samples:  
.1 Submit duplicate 300 x 300 mm samples of siding material, of colour and profile specified.  
.2 Manufacturer's Instructions:  
.1 Submit manufacturer's installation instructions.

## PART 2 - PRODUCTS

- 2.1 STEEL CLADDING AND COMPONENTS .1 Strip siding: to CGSB 93.4, vertical, Class plain.  
.1 Finish coating: Colonite HMP, 8000 + series  
.2 Colour: brown to match previous work.  
.3 Thickness: 0.76 mm base metal thickness.  
.4 Profile: 38 mm deep, preformed interlocking joints.  
Approved products:  
.1 Ideal Roofing - Urban Accent  
.2 Vic West AD300R

---

## 2.2 ACCESSORIES

- .1 Exposed trim: inside corners, outside corners, end cap strip, bottom trim, of same material, colour as cladding.
- .2 Hat Sections: 25 mm legs, 50 mm face, depth as detailed, metal thickness 1.3mm..
- .3 Intermediate battens - 1/2" x 1 1/2" builders channel.

## 2.3 FASTENERS

- .1 Screws: ANSI B18.6.4. Purpose made cadmium plated steel.
- .2 Hat sections and intermediate battens to masonry - 1/4" x 1 1/2" Zamac Pin Bolts.

## 2.4 AIR BARRIER

- .1 Exterior wall vapour permeable membrane and air barrier. sheathing membrane - triple layer spun bond polyethylene.
  - .1 Acceptable Material: WrapShield by Vapro Shield..
  - .2 SRP - AirOutshield Wall by SRP Canada Inc.
- .2 Sheathing tape -
  - .1 VaproTape AB.by Vapro Shield
  - .2 SRP Eternabond Seam seal Tape - Grey by SRP Canada Inc.

## PART 3 - EXECUTION

### 3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.
- .2 .

### 3.2 INSTALLATION


- .1 Install one layer of exterior wall air barrier sheathing membrane with all horizontal laps made in shingle fashion and a minimum of 6". All vertical laps to be a minimum of 12".
- .2 Seal all laps with sheathing tape and all terminations with specified tape.
- .3 Install hat sections at a maximum spacing of 5'-0" c/c with 1/4" x 1 1/2" Zamac Pin Bolts spaced at 12" c/c on leg of hat section - stagger fasteners from one leg to the other.
- .4 Install builders channel at 20" c/c between hat sections with 1/4" x 1 1/2" Zamac Pin Bolts at 32" c/c.
- .5 Ensure that either a hat section or a builders channel fall on every horizontal lap in the membrane to act as a batten .
- .6 Install cladding as per details.
- .7 Install inside and outside corners and bottom drip cap flashings.
- .8 Maintain joints in exterior cladding, true to line, tight fitting, hairline joints.
- .9 Attach components in manner not restricting thermal movement.

3.3 CLEANING


- .1 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

**END OF SECTION**






**1**  
A-1  
SCALE: 1/8" = 1'-0"










**2**  
A-1  
SCALE: 3" = 1'-0"



**3**  
A-1  
SCALE: NTS






  
**Halifax Regional School Board**

KEY PLAN

LOGO


  
**FOWLER BAULD & MITCHELL**  
architecture

Fowler Bauld & Mitchell Ltd.  
PO Box 514, Suite 102  
1660 Hollis Street  
Halifax, Nova Scotia B3J 2R7  
Tel: 902 429 4100  
Fax: 902 423 3063  
architects@fblm.ns.ca  
www.fblm.ns.ca

GRAPHIC SCALE

DATE	MARK	ISSUE

STAMP

  
LICENSED ARCHITECT  
HARVEY F. FREEMAN  
NSA ASSOCIATION OF ARCHITECTS

SCALE: 3" = 1'-0"

DRAWN BY: CFH  
CHECKED BY: HFF  
REVIEWED BY:   
APPROVED BY:   
AS-BUILT CHECK  
DATE: 15 JUL 14

PROJECT  
PROSPECT ROAD  
ELEMENTARY SCHOOL  
RE-ROOF

HATCHET LAKE, NOVA SCOTIA  
PROJECT NO.: 2014-055


SHEET TITLE  
DETAILS

INTERNAL NO.:


**A-2**

SHEET 2 OF 3







**1**  
SECTION DETAIL  
ROOF AT SOFFIT SOUTH SIDE  
SCALE: 3" = 1'-0"




**2**  
SECTION DETAIL  
ROOF JUNCTION AT STUD WALL  
SCALE: 3" = 1'-0"




**3**  
SECTION DETAIL  
ROOF AT SOFFIT WEST SIDE  
SCALE: 3" = 1'-0"



**4**  
SECTION DETAIL  
ROOF AT SOFFIT EAST SIDE - REBUILT  
SCALE: 3" = 1'-0"




**4E**  
SECTION DETAIL  
ROOF AT SOFFIT EAST SIDE - AS TAKEN FROM EXISTING DRAWINGS WITH EXISTING ROOF SYSTEM ALREADY REMOVED  
SCALE: 3" = 1'-0"



**4R**  
SECTION DETAIL  
ROOF AT SOFFIT EAST SIDE - REMOVAL  
SCALE: 3" = 1'-0"






**1** ROOF PLAN  
A-1 SCALE: 1/8" = 1'-0"

- LEGEND**
- ⊕ RD ROOF DRAIN - ALL DRAINS TO BE REPLACES
  - E.F. FANS - RAISE TO 12" ABOVE DRAINAGE PLANE
  - V PLUMBING VENT

- SCHEDULE OF INSULATION THICKNESS AND SLOPES**
1. ROOF 1, 2, 3, 4, 5, 6 AND 7 TO BE 2" AT 2'-0" FROM DRAIN WITH 2% SLOPE.
  2. ROOF 8 AND 9 TO BE 2" AT 2'-0" FROM DRAIN WITH A MAXIMUM THICKNESS OF 6".
  3. SUMP DRAINS BY 1"




LOGO  
**FOWLER BAULD & MITCHELL**  
architecture

Fowler Bauld & Mitchell Ltd.  
PO Box 514, Suite 102  
1660 Hollis Street  
Halifax, Nova Scotia B3J 2R7  
Tel: 902 429 4100  
Fax: 902 423 3063  
architects@fblm.ns.ca  
www.fblm.ns.ca

GRAPHIC SCALE

23 JUL 14 DATE ISSUED FOR TENDER

DATE MARK ISSUE



SCALE 1/8" = 1'-0"

DRAWN BY: MDG

CHECKED BY: HFF

REVIEWED BY:

APPROVED BY:

AS-BUILT CHECK

DATE: 23 JUL 2014

PROJECT  
J.L. ILSLEY  
HIGH SCHOOL  
RE-ROOF &  
WINDOW REPLACEMENT  
SPRYFIELD, NOVA SCOTIA

PROJECT NO.: 2014-059


SHEET TITLE  
ROOF PLAN

INTERNAL NO.:

**A-1**


SHEET OF






**1**  
SECTION DETAIL  
ROOF EDGE AT BRICK - DECK PARALLEL TO WALL

A-2 SCALE: 3" = 1'-0"




**3**  
SECTION DETAIL  
ROOF EDGE - COATED PLYWOOD FASCIAL PANELS

A-2 SCALE: 3" = 1'-0"




**4**  
SECTION DETAIL  
SIDEWALL ON LINE '7'

A-2 SCALE: 3" = 1'-0"



**2**  
SECTION DETAIL  
ROOF EDGE AT BRICK - DECK PERPENDICULAR TO WALL

A-2 SCALE: 3" = 1'-0"




**5**  
SECTION DETAIL  
EXPANSION JOINT

A-2 SCALE: 3" = 1'-0"

3/4" PLYWOOD  
6mil POLY VAPOUR BARRIER  
2x4 WD. STUD AT 24" o/c  
SCREWED INTO BACK  
PLYWD. AT 16" o/c  
R12 FIBERGLAS BATT INSUL.  
3/4" PLYWOOD, NAILED  
2 LAYERS 1/2" RECOVERY BD.  
SCREW AT 1 FASTENER  
PER 2 SQ.FT.  
MOD. BIT. BASE AND CAP  
SHEET





NOTE:  
ROOF 'F' HAS A STEEL DECK BUT DUE TO THE MAXIMUM THICKNESS OF INSULATION IN THE AREA FROM 'E' TO 'F' BEING OVER 11" THICK THE WHOLE ROOF IS BEING ADHERED WITH 2 PART LOW RISE FOAM ADHESIVE.

OVERALL INSULATION THICKNESS IN THIS AREA WILL EXCEED 11" AND MUST BE DONE WITH AN 8" FLAT BASE LAYER AND TAPERED INSULATION APPLIED OVER

METAL SIDING FROM 'A' TO THE OUTSIDE FACE OF THE PARAPET AT 'B'.

1 ROOF PLAN  
A-1 SCALE: 1/16" = 1'-0"

LEGEND

- V - PLUMBING VENT
- F - FAN
- ⊕R.D.- ROOF DRAIN, RAISE AND REUSE.

NOTES

- NOTE 1 - BUILD A CURB FROM LAMINATED 2" x 4" TO 12" ABOVE DRAINAGE PLANE OF THE ROOF AND SPACED 2" FROM CHIMNEY. FLASH CURB TO TOP AND ACROSS THE TOP BUT DO NOT ADHERE MEMBRANE TO CHIMNEY. FLASHING INTO A NEW REGLET WITH METAL ONLY TO BE WATERPROOF.
- NOTE 2 - DECK COVER BOARD FASTENING PATTERN IS TO BE 8 PER 4'-0" x 8'-0" IN FIELD, 12 IN EDGE WIDTH AND 16 IN CORNER.

SCHEDULE OF INSULATION THICKNESS AND SLOPES

- ROOF F - 2" INSULATION THICKNESS AT 2'-0" FROM DRAIN AND 2% SLOPE.  
- SUMP DRAIN 1".

NOTE ALSO - METAL SIDING ON GRID LINE 12.



TYPICAL ROOFING SYSTEM - EXISTING DONE IN 2011  
2 PLY MODIFIED ROOFING MEMBRANE  
3/4" PLYWOOD  
2 LAYERS 1/2" FIBERBOARD  
RIGID INSULATION  
2 PLY FELT AND ASPHALT VAPOUR BARRIER  
1/2" DRYWALL

TYPICAL ROOFING SYSTEM  
TORCHED CAP SHEET  
INSULATION COVER BOARD WITH FACTORY APPLIED BASE SHEET  
ADHERED WITH 2 PART ADHESIVE  
TAPERED INSULATION ADHERED WITH 2 PART ADHESIVE  
AT 2% SLOPE  
TORCHED BASE SHEET AS VAPOUR BARRIER  
5/8" DECK COVER BOARD  
EXISTING STEEL DECK

ADD ONE LAYER OF 3/4" PLYWOOD OVER  
EXISTING PLYWOOD AND EXTEND TO FACE  
OF NEW WOOD BLOCKING SECURE AT 16"  
C/C IN TWO ROWS WITH #12 X 3"  
SCREWS

GRAVEL STOP FLASHING

NEW 2" X 6" BLOCKING ON FACE OF  
PARAPET. SECURE VERTICALLY AND  
HORIZONTALLY AT 12" C/C WITH #12 X  
3" SCREWS

COLOR MATE SCREWS AT 32" C/C

DRY BASE SHEET APPLIED ON TOP  
AND BACK OF PARAPET, BLOCKING,  
AND 4" BEYOND THE EDGE OF  
PLYWOOD AND UNDER DECK COVER  
BOARD.

1/4" RECOVERY BOARD WITH 3 LINES  
OF SCREWS ON TOP OF PARAPET, 3  
LINES ON BACK OF PARAPET, 1 IN  
EACH EDGE OF BLOCKING AND 2  
LINES ON THE PLYWOOD ON FLAT.

EXISTING WOOD FRAMED PARAPET AND 1/2" PLYWOOD ON DECK TO REMAIN -  
REMOVE AND REPLACE EXISTING DRYWALL ON DECK

NOTE:  
WHERE INSULATION THICKNESS EXCEEDS 11" USE  
8" FLAT BASE LAYER WITH TAPERED LAYER OVER.

3  
A-2  
SECTION DETAIL  
TYPICAL ROOF EDGE  
SCALE: 3" = 1'-0"

EXISTING FRAMLINE EXPANSION  
JOINT TO REMAIN

EXISTING EXPANSION JOINT BUILT AS STUD WALLS  
FROM 2" X 6" WITH 3/4" PLYWOOD ON OUTER  
FACES

SELF ADHESIVE VAPOUR BARRIER

EXISTING 1/2" PLYWOOD

TYPICAL ROOFING SYSTEM  
TORCHED CAP SHEET  
INSULATION COVER BOARD WITH FACTORY APPLIED BASE SHEET  
ADHERED WITH 2 PART ADHESIVE  
TAPERED INSULATION ADHERED WITH 2 PART ADHESIVE  
AT 2% SLOPE  
TORCHED BASE SHEET AS VAPOUR BARRIER  
5/8" DECK COVER BOARD  
EXISTING STEEL DECK

DRY BASE SHEET APPLIED ON  
BACK OF PARAPET AND 4"  
BEYOND THE EDGE OF PLYWOOD  
AND UNDER DECK COVER BOARD.

1/4" RECOVERY BOARD WITH 2  
LINES OF SCREWS BACK FACE OF  
PARAPET AND 2 LINES ON THE  
FLAT.

EXISTING MODIFIED  
ROOF DONE IN 2011

NEW 2 PLY MODIFIED ROOF

4  
A-2  
SECTION DETAIL  
EXISTING EXPANSION JOINT  
SCALE: 3" = 1'-0"

REMOVE EXISTING METAL FLASHING AND  
BUILD OUT FOR NEW METAL WALL

FLASHING WIDTH TO MATCH ADJACENT

3/8" THREADED RODS SET IN EPOXY AT 16"  
C/C TO SECURE WOOD BLOCKING TO BRICK

COLORMATE SCREWS AT 32"  
C/C

METAL SIDING AS SPECIFIED

NEW WORK  
REQUIRED UNDER  
THIS CONTRACT  
TO ADD METAL  
SIDING TO SIDE  
WALL AT LINE 12

BUILDER CHANNELS AS BATTENS AT  
1'-8" C/C MAX. SPACING SECURED  
WITH 1" PIN BOLTS AT 24" o/c

1 1/2" DEEP HAT SECTION AT MID HEIGHT

2  
A-2  
SECTION DETAIL  
NEW METAL WALL AT LINE 12 - TIE INTO EXISTING ROOF 'B'  
SCALE: 3" = 1'-0"

EXTEND BASE AND CAP SHEET 6" UP ON BRICK

BUILDER CHANNEL AS TERMINATION BAR  
OVER BOTTOM EDGE OF AIR BARRIER

1/4" RECOVERY BOARD WITH 4 LINES  
OF SCREWS ON THE 2 LAYERS OF  
PLYWOOD AND 2 LINES ON THE  
PLYWOOD ON FLAT.


2 LAYERS 3/4" PLYWOOD SECURED TO  
BRICK WITH 1/4" ZAMAC PIN BOLTS AT  
12" C/C IN TWO ROWS

DRY BASE SHEET APPLIED OVER  
PLYWOOD AND 4" BEYOND THE  
EDGE OF PLYWOOD ON FLAT AND  
UNDER DECK COVER BOARD.


TYPICAL ROOFING SYSTEM  
EXISTING STEEL DECK  
5/8" DECK COVER BOARD  
TORCHED BASE SHEET AS VAPOUR BARRIER  
TAPERED INSULATION ADHERED WITH 2 PART ADHESIVE  
INSULATION COVER BOARD WITH FACTORY APPLIED BASE  
SHEET ADHERED WITH 2 PART ADHESIVE  
TORCHED CAP SHEET

2  
A-2  
SECTION DETAIL  
NEW METAL WALL AT LINE 12 - ROOF/WALL JUNCTION  
SCALE: 3" = 1'-0"






**1**  
A-1  
ROOF PLAN  
AREA 'D'  
SCALE: 3/32" = 1'-0"



**2**  
A-1  
ROOF PLAN  
AREA 'B'  
SCALE: 3/32" = 1'-0"


- NOTES:**
- CRICKET 48" LONG @ 1/8" PER FOOT SLOPE. MAX HEIGHT 2 1/2".
  - REMOVE AND DISPOSE OF PLASTIC PIPE.
  - OWNER WILL REMOVE AHU'S. ROOFER TO RAISE CURBS. OWNER WILL RE-INSTALL UNITS.
  - BUILD A CURB FROM LAMINATED 2X4 TO 12" ABOVE DRAINAGE PLANE OF ROOF AND SPACED 2" FROM CHIMNEY. FLASH CURB TO TOP AND ACROSS THE TOP BUT DO NOT ADHERE MEMBRANE TO CHIMNEY. FLASHING INTO A NEW REGLET WITH METAL ONLY TO BE WATER TIGHT.
  - ROOF DECKS:  
ROOF 'B' - 1/2" METAL DECK  
ROOF 'D' - WOOD DECK
  - SCHEDULE OF INSULATION THICKNESS AND SLOPES  
ROOF 'D' & ROOF 'B' - 6" UNIFORM THICKNESS INSULATION WITH CRICKETS AS DETAILED.

- LEGEND**
- RDN - NEW ROOF DRAIN (ZURN Z-181 6")
  - RDE - EXISTING ROOF DRAIN (TO BE REUSED)




**FOWLER BAULD & MITCHELL**  
architecture

Fowler Bauld & Mitchell Ltd.  
PO Box 514, Suite HS-1  
1660 Hollis Street  
Halifax, Nova Scotia B3J 2R7  
Tel: 902 429 4100  
Fax: 902 423 3063  
architects@fblm.ns.ca  
www.fblm.ns.ca



23 JUL 14  
DATE MARK ISSUE



SCALE 3/32" = 1'-0"  
DRAWN BY: MDG  
CHECKED BY: HFF  
REVIEWED BY:  
APPROVED BY:  
AS-BUILT CHECK  
DATE: 23 JUL 2014

PROJECT  
GROSVENOR WENTWORTH  
ELEMENTARY SCHOOL  
RE-ROOF


HALIFAX, NOVA SCOTIA  
PROJECT NO.: 2014-065

SHEET TITLE  
ROOF PLAN



INTERNAL NO.:

**A-1**  
SHEET OF









**1 ROOF PARAPET - PARALEL TO STRUCTURE**




**3 ROOF DRAIN AT SUMP**



**2 ROOF PARAPET - PERPENDICULAR TO STRUCTURE**



**4 PLAN DETAIL AT ROOF DRAIN SUMP**





TYPICAL ROOF CONSTRUCTION AT PARAPET  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6"± INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
1 LAYER 3/4" RECOVERY BOARD SCREWED AT MAX. SPACING 12"x12"  
BASE SHEET LAID DRY  
3/8" PLYWOOD

TYPICAL ROOF CONSTRUCTION  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6" INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/8" GWB ROOF SHEATING

EXISTING METAL FLASHING RAISED TO ALLOW NEW MEMBRANE TO BE INSTALLED AND FOLDED BACK DOWN  
TERMINATION BAR SECURED AT 6" o/c WITH 3/4" PIN BOLTS

TYPICAL ROOF CONSTRUCTION  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6" INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/8" GWB ROOF SHEATING

9 PIECES OF 2x8 SCREWED TO EACH OTHER WITH #12xAT 16" o/c IN 2 ROWS, STAGGERED  
3/4" PLYWOOD

METAL FLASHING c/w CONT. CLEAT

PEEL & STICK AIR/VAPOUR BARRIER


FIRST TWO PIECES OF 2x8 SECURED TO EVERY HIGH FLUTE WITH 2 SCREWS

DRY BASE SHEET TO EXTEND 3" UNDER DRYWALL

3/4" PLYWOOD TO SPAN 3 HIGH FLUTES AND BE SCREWED TO EACH FLUTE WITH #12 SCREWS AT 12" o/c

DECK PARALLEL TO SIDE WALL.  
NOTE: WHERE DECK IS AT RIGHT ANGLES TO SIDE WALL THE 3/4" PLYWOOD IS TO BE 16" WIDE AND SCREWED TO ROOF DECK AT 12" o/c IN 2 ROWS, STAGGERED

**1** ROOF EDGE AT ROOF B



TYPICAL ROOF CONSTRUCTION AT PARAPET  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6"± INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
1 LAYER 3/4" RECOVERY BOARD SCREWED AT MAX. SPACING 12"x12"  
BASE SHEET LAID DRY  
3/8" PLYWOOD

TYPICAL ROOF CONSTRUCTION  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6" INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/8" GWB ROOF SHEATING

TYPICAL ROOF CONSTRUCTION AT PARAPET  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6"± INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
1 LAYER 3/4" RECOVERY BOARD SCREWED AT MAX. SPACING 12"x12"  
BASE SHEET LAID DRY  
3/8" PLYWOOD

TYPICAL ROOF CONSTRUCTION  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6" INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/8" GWB ROOF SHEATING

8 PIECES OF 2x6 SCREWED TO 3/4" PLYWOOD AND EACH OTHER AT 16" o/c IN 2 ROWS  
CAP SHEET, TORCHED  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/4" RECOVERY BOARD SCREWED AT MAX. SPACING 12"x12"  
BASE SHEET LAID DRY


6" (N.T.S.) 6" (N.T.S.)

EXISTING ROOF CONSTRUCTION


3/4" PLYWOOD SPANNING 3 HIGH FLUTES

DRY BASE SHEET TO EXTEND 3" UNDER DRYWALL

**2** ROOF DIVIDER



**3** SIDEWALL BETWEEN ROOF A & B



TYPICAL ROOF CONSTRUCTION AT PARAPET  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6"± INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
1 LAYER 3/4" RECOVERY BOARD SCREWED AT MAX. SPACING 12"x12"  
BASE SHEET LAID DRY  
3/8" PLYWOOD

TYPICAL ROOF CONSTRUCTION  
CAP SHEET, TORCHED  
INSULATION COVER BOARD c/w FACTORY APPLIED CAP SHEET SECURED WITH 8" SCREWS AND PLATED  
6" INSULATION  
TORCHED 180 SANDED SURFACE BASE SHEET  
3/8" GWB ROOF SHEATING

8 PIECES OF 2x6 SCREWED TO 3/4" PLYWOOD AND EACH OTHER AT 16" o/c IN 2 ROWS  
3 PIECES OF 2x3 SCREWED TO WOOD PARAPET

PEEL & STICK AIR/VAPOUR BARRIER

INFILL WITH BATT INSULATION

3/4" PLYWOOD


METAL FLASHING c/w CONT. CLEAT

DRY BASE SHEET TO EXTEND 3" UNDER DRYWALL

3/4" PLYWOOD 16" WIDE AND SCREWED TO ROOF DECK AT 12" o/c IN 2 ROWS, STAGGERED

EXISTING BRICK VENEER

**4** SIDEWALL AT ROOF B



Halifax Regional School Board

KEY PLAN

LOGO




Fowler Bauld & Mitchell Ltd.  
PO Box 514, Suite HS-1  
1660 Hollis Street  
Halifax, Nova Scotia B3J 2R7  
Tel: 902 429 4100  
Fax: 902 423 3063  
architects@fblm.ns.ca  
www.fblm.ns.ca

GRAPHIC SCALE

23 JUL 14  
DATE MARK  
ISSUED FOR TENDER  
ISSUE

STAMP



SCALE 3" = 1'-0"  
DRAWN BY: MDG  
CHECKED BY: HFF  
REVIEWED BY:  
APPROVED BY:  
AS-BUILT CHECK  
DATE: 23 JUL 2014

PROJECT  
GROSVENOR WENTWORTH  
ELEMENTARY SCHOOL  
RE-ROOF

HALIFAX, NOVA SCOTIA  
PROJECT NO.: 2014-065


SHEET TITLE  
DETAILS

INTERNAL NO.:

**A-3**

SHEET OF





**LEGEND**

- v - PLUMBING VENT
- F - FAN
- GN - GOOSE NECK VENT
- ⊕R.D.R. - ROOF DRAIN REPLACED
- ⊕R.D.E. - ROOF DRAIN, EXISTING TO BE REUSED.

**NOTES**

- NOTE 1 - BUILD A CURB FROM LAMINATED 2"x4" TO 12" ABOVE THE DRAINAGE PLANE OF THE ROOF AND SPACED 2" AWAY FROM THE FACE OF THE CHIMNEY. FLASH WITH ROOF MEMBRANE TO TOP AND ACROSS WIDTH OF CURB BUT DO NOT ADHERE MEMBRANE TO BRICK. CUT A REGLET IN THE BRICK AND FLASH WITH METAL IN A WATER TIGHT MANNER.
- NOTE 2 - OWNER WILL HAVE THE THREE GOOSENECK VENTS AND EXHAUST FANS DISCONNECTED AND REMOVED. ROOFER TO RAISE CURBS TO 12" ABOVE DRAINAGE PLANE OF THE ROOF AND FLASH WITH MEMBRANE. OWNER WILL REINSTALL ALL UNITS.
- NOTE 3 - NEW BILCO HATCH AND ACCESS LADDER. SEE DETAIL 5 ON SHEET A-2.
- NOTE 4 - NEW ACCESS LADDER AND PLATFORM AS PER DETAILS 6, 7, AND 8 ON SHEET A-2.

**ROOF DECKS**


- ROOF 4 - 3/4" T & G WOOD.
- ROOF 5 - 1 1/2" METAL.

**SCHEDULE OF INSULATION THICKNESS AND SLOPES**


- ROOF 4 - 5" INSULATION THICKNESS AT 2'-0" FROM DRAIN AND 2% SLOPE WITH ONE CRICKET.
- ROOF 5 - 9" UNIFORM THICKNESS INSULATION WITH ONE CRICKET.
- SUMP ROOF DRAINS BY 1".

1 ROOF PLAN  
A-1 SCALE: 1/8" = 1'-0"







**1**  
SECTION DETAIL  
ROOF PARAPET  
SCALE: 3" = 1'-0"




**3**  
SECTION DETAIL  
ROOF PARAPET  
SCALE: 3" = 1'-0"




**6**  
PLAN DETAIL  
LADDER PLATFORM & STEPS  
SCALE: 1" = 1'-0"




**2**  
SECTION DETAIL  
DEFLECTION JOINT  
SCALE: 3" = 1'-0"




**4**  
SECTION DETAIL  
ROOF PARAPET  
SCALE: 3" = 1'-0"



**7**  
SECTION DETAIL  
THROUGH PLATFORM & STEPS  
SCALE: 1" = 1'-0"



**5**  
SECTION DETAIL  
THROUGH ROOF HATCH AND LADDER  
SCALE: 3/4" = 1'-0"



**8**  
ELEVATION  
ELEVATION - LADDER TO ROOF AREA #3  
SCALE: 1/4" = 1'-0"

**Halifax Regional School Board**

KEY PLAN

LOGO

**FOWLER BAULD & MITCHELL**  
architecture

Fowler Bauld & Mitchell Ltd.  
PO Box 514, Suite 102  
1660 Hollis Street  
Halifax, Nova Scotia B3J 2R7  
Tel: 902 429 4100  
Fax: 902 423 3063  
architects@fbrm.ns.ca  
www.fbrm.ns.ca

GRAPHIC SCALE

DATE: \_\_\_\_\_ MARK: \_\_\_\_\_ ISSUE: \_\_\_\_\_

STAMP

**LICENSED ARCHITECT**  
HARVEY F. FREEMAN  
NOVA SCOTIA ASSOCIATION OF ARCHITECTS

SCALE: AS SHOWN  
DRAWN BY: CFH  
CHECKED BY: HFF  
REVIEWED BY:  
APPROVED BY:  
AS-BUILT CHECK  
DATE: 23 JUL 2014

PROJECT  
**HILLSIDE PARK  
ELEMENTARY SCHOOL  
RE-ROOF**

SACKVILLE, NOVA SCOTIA  
PROJECT NO.: 2014-061

SHEET TITLE  
**DETAILS**

INTERNAL NO.:  
**A-2**

SHEET 2 OF 2